



79

Survey No. \_\_\_\_\_ for First National Bank of Portland, Oregon.

Purpose of Survey: To establish the boundaries of property described in Deed Records, Volume 296, Page 370, Jackson County, Oregon, part of lots 2 and 3, Block 10, Town (now City of) Central Point, Oregon.

Found and checked for location the center line monuments of the streets (as established by the said city in the year 1908) bounding the said Block No. 10. The intersection of the center lines of Pine and 2nd Street is marked by a granite stone with a cross. The measured distances were found to over run the record distances and the boundaries of the above described premises was monumented in a direct proportion between the measured distance and the record distances.

The North corner is marked by a lead slug in concrete sidewalk with a center punch mark. The other three corners are marked by a 3/4" x 35" iron bolt with square head stamped with a No. 7 on top.

July, 1948

REGISTERED  
OREGON  
LAND SURVEYOR

*C. Z. Boyden*

MARCH 10, 1948  
C. Z. BOYDEN  
7

RECEIVED  
JACKSON  
JUL 30 1948  
COUNTY  
ENGINEER-SURVEYOR