

Survey Narrative to Comply with Section 87, 330, 1947 Oregon State Laws.

91

Survey for: Mr. Martin Heitkamp, located in DIC 50, Twp 37 South, Range 1 West of the Willamette Meridian, Jackson County, Oregon.

Purpose of Survey:

To stake, and describe five tracts of land, size and shape designated by Mr. Heitkamp.

Survey Procedure:

Located a 2" galvanized iron pipe which is the NW corner of D. L. C. No. 50, run thence along the West boundary of D. L. C. No. 50 $30^{\circ}09'10''$ E 981.83 feet (bearings computed by solar observation) to an iron pin on the South line of Barnett Road, run thence along the the South line of said road, $N89^{\circ}57'E$, thence $S0^{\circ}09'E$ 520.60 feet to a one inch iron pipe on gulley bottom, said pipe being the NE corner of tract 5, run thence $S0^{\circ}09'E$ to intersect the center line of the creek, thence along the existing center line of creek the following courses: $S88^{\circ}42'20''W$ 152.10 feet, $S85^{\circ}36'W$ 217.94 feet, $N34^{\circ}26'W$ 93.00 feet, and $N3^{\circ}0'E$ 486.60 feet to point which is $S89^{\circ}57'$ from the point of beginning, run thence $N89^{\circ}57'E$ 394.70 feet to the point of beginning.

Pipe set on corners as shown by attached plat, $3/4''$ X 18" pipe also set on lot lines and bank of creek at breakoff.

J. H. Clabby

August 1948

