

110

116

WHITE CITY

SECS. 16,17,18,19,20 & 21, T36S. R1W.

NOV. 1948

REGISTERED
OREGON
LAND SURVEYOR

C. Z. Boyden

MARCH 10, 1944
C. Z. BOYDEN
7

N

SCALE - 1" = 500'

- 1" IRON PIN
- 1" IRON PIN IN CONCRETE
- ◎ 3" BRASS DISC IN CONCRETE



VETERANS HOSPITAL

S 89°48' E 3544.99

S 0°12' W 1579.50

S 89°48' E 2777.10

E AVE. - G -

ROAD

18 17
19 20

17 16
20 21

4180.50

S 0°12' W

5170.50

N 0°12' E

11TH St.

LITTLE BUTTE

50'

30'

E AVE - B - 100' R/W

S 89°48' E 4118.0

N 89°48' W 4931.09

N 89°48' W 5509.0

ARMY ENG. MON.

E AVE - A -

116

Survey No. 116 for White City Lumber Company

Purpose of Survey: To establish and monument the boundary of a tract of land in the Camp White military reservation to be known as White City.

Began at a 3" brass disc, army engineers monument, set to be intersection of Avenue "A" and Little Butte Road, which point is S. 89° 48' E. 1.0 feet from the 1/4 section corner between Sections 19 and 20, Township 36 South, Range 1 West; ran thence N. 89° 48' W. along the center line of Avenue "A" 4931.09 feet to a point 30.0 feet Easterly from the center line of 4th Street; thence N. 0° 12' E., 30.0 feet Easterly from the center line of 4th Street 589.5 feet to a point 50.0 feet Southerly from the center line of Avenue "B".

Then by offset lines established points as follows: S. 89° 48' E., 4118.0 feet to an intersection point 50.0 feet Southerly from the center line of Avenue "B" and 30.0 feet Westerly from the center line of 11th Street; thence N. 0° 12' E. 5170.50 feet to a point 30.0 feet Westerly from the center line of 11th Street extended; Thence S. 89° 48' E. 3544.99 feet to a point 30.0 Westerly from the center line of 18th Street extended; thence S. 0° 12' W. 1579.50 to a point of intersection being 30.0 Westerly from the center line of 18th Street and 50.0 feet Northerly from the center line of Avenue "G"; thence S. 89° 48' E. 2777.10 to a point 50.0 feet Northerly from the center line of Avenue "G"; thence S. 0° 12' W. 4180.50 feet to the center line of Avenue "A"; thence along the center line of Avenue "A" N. 89° 48' W. 5509.0 feet to the place of beginning.

Monuments stamped with a No. '7' set for corners as shown on the map to accompany this report.

Survey completed November, 1948.

C. Z. BOYDEN

