



174



Note: Iron pipe set at property corners

PLAT SHOWING A SURVEY MADE
 FOR J. VERNE SHANGLE,
 D.R. Vol. 244, P 87,
 LOCATED T37S, R2W WM
 Jackson County, Oreg
 Scale - 1" = 60' June 17, 1949
 J.H. CLABBY, CONSULTING ENGINEER

COUNTY ROAD 1/4 W LINE

WEST LINE, D.L.C. '85

R/W LINE

SOUTH LINE D.L.C. '85



174

Survey Narrative to Comply with Section 87, 330, 1947 Oregon State Laws.

Survey for: Mr. J. Verne Shangle

D. I. C. No. 85, Township 37 South, Range 2 West, Willamette Meridian
Jackson County, Oregon.

Purpose of Survey:

To locate property boundaries.

Survey Procedure:

Found northwest corner and southwest corner monuments of D. I. C. No. 85, Township 37 South, Range 1 West, Willamette Meridian, ran North 0° 08' 30" East along west line of D. L. C. 85 from southwest corner 1000.00 feet and set a 1" iron pipe for the point of beginning, ran thence North 89° 36' 00" East 360.71 feet and set a 1" iron pipe, thence North 0° 08' 30" East 235.50 feet and set a 1" iron pipe, thence west 157.00 feet and set a 1" iron pipe, thence South 80° 32' 30" West 157.00 feet and set a 1" iron pipe, thence South 81° 30' 00" West 48.80 feet and set a 1" iron pipe, thence South 0° 08' 30" West 205.00 feet to the point of beginning.

J. H. Clabby

