



N 00° 01' 30" W
2603.00'
WEST LINE, D.L.C. 59

S.W. COR., D.L.C. 59

POINT OF BEGINNING
(I.P.)

N 57° 48' 30" E (REC. N 58° 08' E)
179.00'

(I.P.)

N 23° 36' 15" E
50.00'

E IRRIGATION DITCH

0.41 ACRES
±
S 65° 18' 15" W
358.92'

N 57° 48' 30" E (REC. N 58° 08' E)
315.22'

(I.P.)

(I.P.)

SW RIGHT OF WAY,
MERRIMAN ROAD

LC
(S 31° 40' 28 1/2" E
74.99')

CURVE DATA
Δ = 00° 22' 33"
D = 00° 30' 04"
R = 11,432.12'
L = 75.00'
LC = 74.99'



BOUNDARY · LOCATION

G. G. BLACK PROPERTY

Located in Donation Land Claim No. 59,
T37S, R2W of Willamette Meridian,
Jackson County, Oregon

August 8, 1949

Scale: 1" = 50'

SURVEY NO. 197

Survey Narrative to Comply with Section 87-330, 1947 Oregon State Laws.

Survey for: G. G. Black
D.L.C. 59, Township 37 South, Range 2 West, Willamette Meridian
Jackson County, Oregon.

Purpose of Survey:

To describe a parcel of land to be sold and to place monuments on same.

Survey procedure:

Located northwest corner D. L. C. 60 and southwest corner D.L.C. 59,
Township 37 South, Range 2 West, Willamette Meridian and established bearing
from same. Ran thence North 0° 01' 35" West 2603.00 feet and set a 1" iron
pipe for the point of beginning, ran traverse around parcel.

J. H. Clabby

August 1949

