



Survey No. 228

For: D. W. Paulsen & M. J. Gates

Purpose: To establish the boundary lines of Lot No. 6, Block No. 10, Original Town, Central Point, Oregon.

Procedure:

Found the centerline monuments enclosing Block 10, which were established in the following manner: The granite stones on Pine Street at 1st and 2nd Streets were established by the City survey of 1908; the concrete monument at 1st and Oak Streets was established by the City survey of 1910, and the iron pipe at 2nd and Oak Streets was set by myself in 1948, using also the 1910 centerline monuments at 3rd and Oak Streets and at 2nd and Alder Streets to make the intersection.

Measured the distances between the monuments around said Block, and from said information subdivided the Block on a proportion between record and measured distances, and monumented Lot 6 as shown on the attached plat.

Special note should be made regarding the two northerly corners of the lot which were not actually set but referenced by lead slugs in the sidewalk set on the lot lines extended one foot out into Pine Street.

March - 1950



*C. Z. Boyden*

