

SURVEY FOR
EDWIN V. ANDERSON

BY ORDER OF: D. W. PAULSEN & M. J. GATES

ORIGINAL TOWN CENTRAL POINT
MAR. 1950

40 N 54°-51'-30" E 280⁷⁶

PINE ST.

40

Leads offset 1⁰ FT.

30

30

27.595

30

30

140.18

140.18

27.60

10

380⁸⁰

ST. ST.

380⁸⁰

2ND ST.

- GRANITE STONE
- ⊙ CONCRETE MONUMENT
- IRON PIPE
- IRON PIN
- LEAD IN SIDEWALK

SCALE:
1" = 60'

40

280⁸⁰

OAK ST.

40

3RD ST.

REGISTERED
OREGON
LAND SURVEYOR

C. Z. Boyden & Alder St.

MARCH 10, 1944
C. Z. BOYDEN
7

May 5, 1950
COUNTY

Survey No. 229

For: Edwin V. Anderson

Purpose of Survey: To locate and monument Lot 5, Block 10,
Original Town, Central Point, Oregon.

Procedure:

Found the official centerline street monuments at First and Pine, Second and Pine, First and Oak Streets; and the iron pipe previously set by myself at Second and Oak Streets (having used also the official centerline street monuments at Third and Oak, and Second and Alder Streets to make the intersection.)

Measured the distances between the monuments around said Block, and from said information sub-divided the Block on a proportion between record and measured distances, and monumented said lots as shown on the attached plat.

Special note should be made regarding the two corners bordering Pine Street. The actual corners were not set, but referenced by lead slugs in the sidewalk set on the lot lines extended one foot out into said street.

March, 1950



C. Z. Boyden

