

SURVEY FOR  
C. C. BROWN

BY ORDER OF: GUY TEX

ORIGINAL TOWN - CENTRAL POINT, ORE.  
APR. 1950.

MANZANITA ST.

- GRANITE STONE
- ⊙ CONCRETE MONUMENT
- IRON PIPE
- IRON PIN
- LEAD IN SIDEWALK

SCALE:  
1" = 60'

FIRST ST.

SECOND ST.

PINE ST.

REGISTERED  
OREGON  
LAND SURVEYOR

*C. Z. Boyden*

MARCH 10, 1944  
C. Z. BOYDEN

7

Survey No. 236

For: C. C. Brown

Purpose of Survey: To locate and monument Lot 12, Block 11,  
Original Town, Central Point, Oregon.

Procedure:

Found the official centerline street monuments at First and Pine, Second and Pine, First and Manzanita Streets, and set an iron pin at Second and Manzanita Streets, using also the official centerline street monuments at Third and Manzanita and Second and Laurel Streets to make the intersection.

Measured the distances between the monuments around said Block and from said information sub-divided the Block on a proportion between record and measured distances, and monumented said lot as shown on the attached plat.

Special note should be made regarding the two corners bordering Pine Street. The actual corners were not set, but referenced by lead slugs in the sidewalk, set on the lot lines extending one foot out into said street.

April, 1950.

REGISTERED  
OREGON  
LAND SURVEYOR

*C. Z. Boyden*

MARCH 10, 1944  
C. Z. BOYDEN  
7

