

1/4 SEC. COR 35/36

FOUND STONE AS DESCRIBED IN GOV'T FIELD NOTES (1897)
BOTH BT'S IN GOOD CONDITION

252

E 1/4 COR. SEC. 36.

FOUND STONE AS DESCRIBED IN GOV'T FIELD NOTES (1912)
SW BT (INTACT)
NW BT (MISSING)

SURVEY FOR
THREE PINES LUMBER CO.
SEC. 36 - T32SR4W.
MAY 1950.

REGISTERED
OREGON
LAND SURVEYOR

C. Z. Boyden
MARCH 10, 1944
C. Z. BOYDEN
7

Gov't RECORD : 50°-01'E , 39.10 chs = 3900.6 FT.

MEASURES 3869.9 FT

2619.2

1250.7

DR 298 - 112-4 (Tbr. Only)

SET 1/2" IRON PIPE FOR THE SW COR. GOV'T LOT #8

SET 2 BT'S - (SEE OFFICIAL RE-ESTABLISHED INTERMEDIATE CORNERS RECORD).

SET 1/2" IRON PIPE FOR THE SE COR. OF GOV'T LOT #5

SET 2 BT'S - (SEE NOTE OPPOSITE).

Gov't RECORD : 50°-19'E , 59.81 chs = 3947.46 FT.

MEASURES 3938.4 FT.

2633.9

1304.5

SW COR. SECT. 36

FOUND OLD STAKE LYING ON GROUND - 2 BT'S IN GOOD CONDITION AS DESCRIBED IN GOV'T FIELD NOTES (1897)

9

10

11

12

DR 225 - 170-3

SE COR SECT. 36

FOUND STONE AS DESCRIBED IN GOV'T FIELD NOTES (1912)
NW BT (GOOD CONDITION)
NE BT (MISSING)



SCALE :
1" = 600'

July 21, 1950

Survey No

252

SURVEY NARRATIVE TO COMPLY WITH SECTION 87-330 ,

1947 Oregon State Law.

Survey No. 252

For: Three Pines Lumber Company

Purpose: To locate and monument the SE corner of Government Lot #5, and the SW corner of Government Lot #8 in Section 36, Township 32 South, Range 4 West.

Procedure: From the S.E. corner of Section 36, ran a traverse northerly to the Quarter Section corner on the East boundary of said section. Calculated the true distance between said corners and located the lot corner on a proportioned distance between measured and Government record distances. Repeated the same procedure on the West boundary of said section, measuring the distance between section and quarter corners and locating the lot corner by proportion. Definite evidence was found for all Government corners used as shown on the plat hereon attached.

May - 1950



C. Z. Boyden
 MARCH 10, 1944
 C. Z. BOYDEN
 7

