



SCALE: 1"=200'

- IRON PIN
- IRON PIPE

SURVEY FOR
 RUCH SCHOOL DISTRICT NO. 3
 SEC. 27 T38SR3W
 AUG. 1950

REGISTERED
 OREGON
 LAND SURVEYOR

MARCH 10, 1941
 C. Z. BOYDLEN

Survey Narrative to comply with Section 87-330 Oregon State Law 1947

Survey No. — ~~273~~

For Ruch School Dist. No. 3

Purpose of survey: To establish the boundaries of the present school lot and to survey and monument an additional tract to be purchased. All located in Section 27, Township 38 South, Range 3 west.

Found the S. W., S. E. and N. E. corners of the present school lot as monumented and described by surveyor G. Elksnot.

Since the $\frac{1}{4}$ section corner between sections 27 and 28 is a lost corner, it was not considered advisable to establish said corner and the East and West center line of Section 27. It was agreed by the parties concerned to establish the line for the purpose of this survey by exchanging deeds.

Then began at the ^{last} officially re-established $\frac{1}{4}$ section corner between sections 26 and 27 and ran N 88° 17' W 2294.07 feet to a point on the Northwesterly boundary of the County Road for the point of beginning, said point being on the extension of the Southerly boundary of the tract described in D. R. 312 -- 49;

Thence N 85° 48' 45" W to and along the Southerly boundary of said tract 331.7 feet to the Southwest corner thereof;

Thence N 87° 46' 10" W 442.06 feet to the iron pin at the N. E. Corner of the present school lot. Then from the iron pin at the S. E. Corner of the present school lot ran S 87° 59' E 652.37 feet to the Northwesterly boundary of the said County Road, being an extension of the Southerly boundary of the present school lot;

Thence along the Northwesterly boundary of the County Road to the point of beginning. Monuments were set as shown on

the map to accompany this report.

August, 1950



C. Z. Boyden
MARCH 10, 1950
C. Z. BOYDEN
7

