



Survey Narrative to Comply with Sec. 87-330, 1947 Oregon State Laws.

303

Survey for: Mills Clark

Location: Southeast Quarter of Southwest Quarter Section 17, Township 33 South, Range 2 East, Willamette Meridian, Jackson County, Oregon

Purpose of Survey:

To verify boundary of piece to be sold.

Procedure:

Beginning from an iron pin set as the southeast corner of the southwest quarter of southwest quarter of southwest quarter, Section 17, Township 33 South, Range 2 West, Willamette Meridian, Jackson County, Oregon, ran traverse course north 62.86 feet, thence North 2° 43' West 196.95 feet, thence North 6° 42' East 196.91 feet, thence North 3° 38' East 97.09 feet, thence North 16° 55' East 206.76 feet, thence South 75° 30' East 119.66 feet, thence North 80° 08' East 171.58 feet, thence South 3° 31' East 162.20 feet, thence South 51° 27' East 136.50 feet, thence South 59° 29' East 196.39 feet, thence South 10° 11' East 170.65 feet, thence North 87° 40' West 99.82 feet, thence South 76° 52' West 131.84 feet, thence North 89° 26' West 184.43 feet, thence South 80° 10' West 70.12 feet, thence South 50° 07' West 140.76 feet, thence South 62° 55' West 101.84 feet to the point of beginning.

All bearings based on solar observation.

Pins were set at points agreed upon by the purchaser of the property. The pins set were tied into the traverse.

Measurements were made on the creek marking the east boundary of the property and center line of the highway forming north boundary.

All points were coordinated and boundary distances and bearings computed.

All pins set were set as witness corners because of the locations of the true property corners, and are shown on the plat attached.

J. H. Clabby

September 1950

