


**BOUNDARY LOCATION
PROPERTY SITUATE IN
LOT 8 BLOCK 4 COTTAGE ADD.
AND LOT 2 BLOCK 13 BEATTY ADD
TO THE CITY OF MEDFORD
JACKSON COUNTY OREGON**

J H CLABBY CIVIL ENGINEER
MEDFORD OREGON 12 FEBRUARY 1951
SCALE 1" = 50'



Page 216

Survey Narrative to Comply with Section 87-330, 1947 Oregon State Laws.

Survey for: Consolidated Freightways Terminal Company
Lot 2, Block 11, Beatty Addition, City of Medford, Jackson County,
Oregon.

Purpose of Survey:

To establish property lines.

Survey Procedure:

Found iron pipes set for southeasterly corner of Lot 2, Block 11, Beatty Addition to the City of Medford, Jackson County, Oregon. Using line between center line markers on Central Avenue as City Engineer's record bearing North 35° 30' West ran thence North 35° 30' West 80.00 feet and set iron pipe for Southeast corner Lot 3, Block 12, continued thence North 35° 30' West 186.00 feet and set iron pipe for property corner, ran thence South 54° 30' West 340.00 feet and set iron pipe, thence South 35° 30' East 226.00 feet and set iron pipe, thence North 54° 30' East 100.00 feet and set iron pipe, thence North 35° 30' West 40.00 feet and set iron pipe.

J. H. Clabby

February 1951

