



Survey Narrative to Comply with Section 87-330, 1947 Oregon State Laws.

Survey for: Julia Canfield
Section 17, Township 38 South, R. 1 W., W.M., Jackson County,
Oregon.

Purpose of Survey:

Boundary location.

Survey Procedure:

Found iron pipe at Quarter Section corner common to Sections 16 and 17, Township 38 South, Range 1 West and iron pipe at intersection of Fort Baker and Coleman Creek Roads. Measured distance as 1021 feet instead of 1019.5 feet per record.

Accepted bearing used on road survey as shown on county road map, ran West 1044.81 feet from said quarter corner, thence South 655.7 feet for true point of beginning and staked the following described property South 0° 05' East 197.40 feet, North 89° 41' 30" West 480.00 feet, North 18° 54' 20" West 78.55 feet, North 4° 23' 40" East 96.65 feet, North 83° 34' East 191.22 feet, North 89° 29' 40" East 307.48 feet to point of beginning.

Staked as shown on plat.

J. H. Clabby

April 1951

