



**BOUNDARY LOCATION
PROPERTY SITUATE IN
N.W. 1/4 SEC. 31 T. 37 S. R. 1 W. W.M.
JACKSON COUNTY, OREGON.**

**J. H. CLABBY. CIVIL ENGINEER
MEDFORD, OREGON. 11 APRIL 1951**

SCALE, 1" = 50'

Sec. 31, T37S, R1W, W. 366

Survey Narrative to Comply with Section 87-330, 1947 Oregon State Laws.

Survey for: W. E. Driscoll
Located corner Stewart and Oakdale Avenues, Medford, Oregon

Purpose of Survey:

Boundary survey.

Survey Procedure:

Located Southwest corner of D.L.C. 44, Township 37 South, Range 1 West, Willamette Meridian, Jackson County, Oregon as recorded in County Court House. Found monument at centerline intersections of Stewart Avenue and Belmont Street.

Established line between said monument and D.L.C. corner.

Measured North on said line and set points 24.33 feet and 124.33 feet from D.L.C. corner. Turned 90° (North to West) from these points and set corners 30 feet and 155 feet from center line of Oakdale Avenue.

Parcel of land being 100 feet North and South by 125 feet East and West.

Set 5/8" iron pins at all corners as shown on plat.

J. H. Clabby

April 1951

