



STAKE 2 ACRE TRACT FOR MRS. MACE.  
 JULY 28 1951

IN SEC 26. T 37S, R 1W. (W.M.)  
 JACKSON COUNTY, ORE.

REGISTERED  
 OREGON  
 LAND SURVEYOR  
*L. N. Dow.*  
 MAY 6 1943  
 L. N. DOW  
 251

Written narrative to accompany plat for survey No. 368  
as specified by Oregon Law.

Date of Survey July 28, 1951.

For Mrs. Mace

Location Metes and Bounds property in Section 26, T 37 S . R 1 W.

Purpose of survey to stake out 2 acre tract for sales purposes.

Procedure; Began at a large iron Pipe at the center of Section 26, T 37 S, R 1 W. (W.M.) and ran south on the center of the section a distance of 369.50 feet to an iron pipe on the northerly right of way of the county road (Cherry Lane) Thence N 51° 11' W 941.18 feet along the said northerly right of way a distance of 941.18 feet to an iron pipe at the south east corner of Mrs. Maces Property. Thence continuing N 51° 11' 818.06 feet and set a 5/8" x 30" Iron Bar for the point of beginning. Ran thence N 38° 49' E 418.91 feet and set a 5/8" x 30" Iron Bar for the northeast corner of Two acre tract, Ran thence N 89° 44' W 365.32 feet to a 1" iron pipe; thence ran S 38° 49' W 191.25 feet along the east boundary of deed 352-156 to a 1" iron pipe on the northerly Right of way of the county road; thence ran S 51° 11' E along the said northerly right of way of the county road a distance of 285.70 feet to the point of beginning.

