



BOUNDARY LOCATION
 PROPERTY SITUATE IN
 SEC. 26 T.37S., R.1W., W.M.
 JACKSON COUNTY, OREGON

J.H. CLABBY CIVIL ENGINEER
 MEDFORD, OREGON. 25 MAY 1951

SCALE; 1" = 200'

Survey Narrative to Comply with Section 87-330, 1947 Oregon State Laws.

Survey for: Helen Mace

Location: Section 26, Township 37 South, Range 1 West, Willamette Meridian
Jackson County, Oregon

Purpose of Survey:

To establish boundary line of two separate parcels of land.

Survey Procedure:

Found iron pipe at center of Section 26, Township 37 South, Range 1 West, South 369.5 feet from said iron pipe along North and South fence line found another iron pipe on the northeasterly right of way line of County Road known as Cherry Lane.

Near the center of Section 27, Township 37 South, Range 1 West found 10" x 10" granite monument with cross which is the Northeast corner of D. L. C. No. 58 and which is on the South right of way line of County Road Station 37 + 80. At Station 70 + 40 and Station 72 + 81 found iron pipes on P.C. and P.T. of said road. At Station 71 + 65.3 found iron pipe at the P.I. of curve. Turned deflection angle from P.I. to right of 38° 33' to bearing of South 51° 11' East along County Road. Established property corner at North and South fence line 30 feet from center line. Set up at the south P&C at Station 70 + 40, using Northeast corner of D.L.C. No. 58 as a backsite and projected ahead on line with an east and west fence at a bearing of South 89° 44' East a distance of 1165 feet to the north end of a fence and set a pin, thence running South 8° 02' West a distance of 845.17 feet to a point on northerly right of way line of County Road which is 941.18 feet, North 51° 11' West from iron pin above mentioned.

June 1951

J. H. Clabby

