



BEARINGS BASED ON RECORDS OF COUNTY SURVEYOR

BOUNDARY LOCATION
 PROPERTY SITUATE IN
 SE 1/4 SEC 17 T 38 S R 1 W WM
 JACKSON COUNTY, OREGON

LELAND P LOVEJOY LAND SURVEYOR
 MEDFORD, OREGON 3 JULY, 1951.

SCALE 1" = 100'

Survey Narrative to Comply with Section 87-3301947 Oregon State Laws

Survey for: R. M. Swan
Medford, Oregon

Purpose of Survey: To locate property boundaries.

Survey Location: Southeast Quarter (1/4) of Section 17, Township 38 South, Range 1 West, Willamette Meridian, Jackson County, Oregon.

Survey Procedure: Found hub at Quarter (1/4) corner Sections 16 and 17, Township 38 South, Range 1 West, Willamette Meridian, with iron reference pipe to South, per record. Found iron bridge spike at intersection of center lines of Camp Baker Road and Wildwood Park Road. Checked record distance of 676.43 feet between Quarter (1/4) corner and spike. Found referenced hub at North end of Wildwood Park Road center line per record. Accepted record bearing of North $6^{\circ} 14'$ West for said center line and ran 757.27 feet northerly. Turned angle $90^{\circ} 00'$ right and set iron pipe at 30.00 feet distance. Continued on same bearing 313.55 feet and set iron pipe. Turned angle left $90^{\circ} 00'$ and set iron pipe 252.55 feet distance. Turned angle 90° left and set iron pipe 313.55 feet distance. Continued line 30.00 feet to center line of road and checked closing angle $90^{\circ} 00'$ and distance 252.55 feet.

Leland P. Lovejoy, Registered Land Surveyor

