



Found 1/2" I.P. In Concrete On West LINE KEENE WAY

Found 2" I.P.

Set 1" G.I.P. at corners

Found 1/2" I.P. On East LINE BERKELEY WAY

OREGON  
 OCT 25 1951  
 L. LOVEJOY  
 ENGINEER-SURVEYOR

OREGON  
 LAND SURVEYOR

*Leland P. Lovejoy*  
 NOVEMBER 18, 1949  
 LELAND P. LOVEJOY  
 262

**PROPERTY SURVEY**  
**LOTS 6, 7, 8, 9 & 10, BLOCK 8**  
**HIGHCROFT ADDITION**  
**TO CITY OF MEDFORD OREGON**  
 MEDFORD JACKSON COUNTY OREGON  
 LELAND P. LOVEJOY REG. SURVEYOR  
 MARCH 31, 1951 SCALE 1" = 60'

Survey Narrative to Comply with Section 87-3301947 Oregon State Laws

Survey for:

Mr. R. E. Marsh  
Medford, Oregon

Purpose of Survey: To determine property corners of Lots 6, 7, 8, 9 and 10, Block 8, of the Highcroft Addition to the City of Medford.

Survey Location: Block 8, Highcroft Addition, City of Medford, Jackson County, Oregon.

Survey Procedure: Located 1/2" G.I.P. at the Southeast corner of Lot 6, Block 8, of said Addition. Said pipe was 2 feet below the surface. Located a 1/2" G.I.P. on the Easterly side of Hillhouse Street and the Northerly side of Crown Avenue. The distance between this pipe and the pipe previously mentioned was 50.00 feet. Found a 1/2" G.I.P. on the Easterly side of Berkeley Way and the Northerly side of Crown Avenue. All three pipe were on a common line. Located a 2" I. pipe on the Southerly line of Crown Avenue (opposite Block 8) and a 1/2" G.I.P. in concrete on the Westerly line of Keene Way and the Southerly line of Crown Avenue. Both pipe proved to be 60.00 feet from the line previously established. Searched for the original corners on Grace Street, but found nothing. Located the Southeast and the Northeast corners of Lot 4 of said Block. The distance along the Easterly line of Block 8 proved to be 0.10 foot short. Made the East line of Lot 6 155.70 feet long. Found a 3/4" I. pipe at Northeast corner Lot 10, which checked. Set the North and South lot lines parallel to Hillhouse Street, and the East and West lot lines parallel to Crown Avenue. Set 1" iron pipe at lot corners.

Leland P. Lovejoy, Registered Land Surveyor

Work completed May 27, 1951.

