

ELL COR. D.L.C. NO. 55

O. HAMILTON
AND
M. E. LAMB

LOCATED IN THE CITY OF CENTRAL POINT
ALSO D.L.C. NO. 55 AND SECTION NO. 2,
T. 37 S., R. 2 W.

MARCH 1950

D.R.
254-276-8

LAMB

N 89°55'30"E

98.0

N 89°55'30"E

132.0

0.66 GAP

27.06

D.R.
299-323

242.27

S 71°15'W

D.R.
256-523

90.02

HAMILTON

REGISTERED
OREGON
LAND SURVEYOR

C. Z. Boyden

MARCH 10, 1944
C. Z. BOYDEN
7

N

SCALE 1" = 40'

⊙ 1 1/2" PIPE REESTAB. D.L.C. COR.
• PIPES SET

N 0°24'W

50.50

123.63

12.65

N 89°55'30"E

240.24

N 0°24'W

208.40

PECK

208.40

S 0°24'E

240.24

S 89°55'30"W

462.16

S.W. COR. D.L.C. NO. 55

RECEIVED
JACKSON
17 1952
COUNTY
ENGINEER-SURVEYOR

SURVEY NARRATIVE TO COMPLY WITH SECTION 87-330,
1947 OREGON STATE LAW

Survey No. 429

For: O. Hamilton and M. E. Lamb

Purpose of Survey: To establish the boundaries of two tracts
of land to be exchanged.

Procedure: Established the west boundary of D.L.C. No. 55
between the officially re-established southwest corner and the
westerly ELL corner, then established the corners of the Hamilton
and Lamb properties on this D.L.C. line according to their
officially recorded deeds; then determined the location of the
street along the Northeasterly boundary of Pattison Addition to
Central Point from the old stakes found along the boundary of
said addition.

From the above mentioned controls staked the boundaries of
the tracts as shown on the map to accompany this report.

A comparison of the record descriptions of the properties
indicates a gap between the two of one link along Hamilton's
north line.

March - 1950

REGISTERED
OREGON
LAND SURVEYOR

C. Z. Boyden

MARCH 10, 1944
C. Z. BOYDEN
7

