



ROGUE RIVER

BOUNDARY LOCATION
 PROPERTY SITUATE IN
 NE ¼ SEC 21 T 34 S RIW WM
 JACKSON COUNTY OREGON
 L P LOVEJOY LAND SURVEYOR
 MEDFORD OREGON 14 APRIL 1952
 SCALE - 1" = 100'

Survey Narrative to Comply with Section 87-3301947 Oregon State Laws

Survey for: Bishop Bros.
Shady Cove, Oregon

Purpose of Survey: To determine property boundary

Survey Location: Northeast One-Quarter (1/4) of Section 21,
Township 34 South, Range 1 West, Willamette
Meridian, Jackson County, Oregon.

Survey Procedure: Ran traverse from monument for section corner
common to Sections 21, 22, 27, and 28, Township 34
South, Range 1 West, Willamette Meridian, to
monument for One-Quarter (1/4) corner common to
Sections 21 and 22, said Township and Range,
taking solar observations to determine true bearing.
Continued traverse and tied in existing iron pipe
designating property corners at Northwest and
Northeast corners. Closed traverse by looping
back to original starting point at section corner
common to Sections 21, 22, 27, and 28, said Township
and Range. Set 1" iron pipe at Southeast and
Southwest property corners.

Leland P. Lovejoy, Registered Land Surveyor

Work completed January 24, 1952

