



Survey Narrative to Comply with Section 87-330. Oregon State Law, 1947.

Survey No. ~~470~~

For: Verl G. Walker

Purpose: To establish the boundaries of Lot No. 6, Block No. 2, Page Addition to Medford.

Procedure: At the time of this survey Haven Street was under construction for improvement and the street centerline monuments except Columbus and Holly have been destroyed as reported by the City of Medford survey party. However: references were furnished by said party for the monument at Haven and Oak Streets, said references having been established prior to destruction of the monument. In cooperation with the city engineer's office, established a center for Woodstock and Haven Streets by proportioning the distance between Oak and Holly Streets.

From this center at Woodstock & Haven and the official street centerline monuments at the other three corners of said Block No. 2, established the boundaries enclosing said block, and determined the boundaries of said Lot 6, by a direct proportion between record and measured distances and monumented same with 5/8" iron pins as shown on the map to accompany this report.

August 6, 1952



*C. Z. Boyden*

