

5677

475

PARKER
DR 325 - 53

PI = Rd. STA. 6+72.2

SOUTHERN PACIFIC RAILROAD

TOLO - WHITE CITY LINE

NORTH BDRY. 1322.00 (DR 299-379)

S. BDRY. S.P. Co. (AS OCCUPIED)

N 89° 41' 40" W

SOUTH BDRY (DR 325-53)

208.00

NORTH BDRY. (DR 288-567)

Fd. PIPE WITH
PIN INSIDE
(Re: DR 280-47)

S 0° 00' 55" E 208.00

HUGHES

208.00

N 0° 00' 55" W 1193.90
KIRTLAND ROAD

SCALE: 1" = 60'

● IRON PIN
○ IRON PIPE

SURVEY FOR
SOUTHERN OREGON TITLE CO.

SEC. 20 T36S R2W

JUNE 1952

MERIDIAN CONTROL:
UNITED STATES GEOLOGICAL SURVEY
TRIANGULATION DATUM

S 89° 41' 40" E 208.00

30.00 30.00

Rd. STA. 0+00.

E_{1/2} cor.

N 89° 56' W 1294.20 - 20/21

29/28

REGISTERED
OREGON
LAND SURVEYOR

C. Z. Boyden

MARCH 10, 1944
C. Z. BOYDEN
7

WRIGHT
DR 288 - 567 - 569

RECEIVED
JACKSON
SEP 12 1952
COUNTY
ENGINEER SURVEYOR

475

Survey Narrative to Comply with Section 87-330, Oregon State Law, 1947.

Survey No. 475

For: Southern Oregon Title Co., Property located in Section 20,
Township 36 South, Range 2 West.

Purpose: To establish the boundaries a tract of land as directed and prepare a description of same.

Established the location of Kirtland road by replacing points on record angles and distances from the P.I. at Engineers' station $23 + 77.7$ to station $0 + 00$. Then projected the tangent from station $6 + 72.2$ thru station $0 + 00$ to an intersection with the section line between sections 20 and 29 for a tie to the SE corner of Section 20.

Established the south boundary of the Southern Pacific Company property for the Tolo to White City Railroad by intersecting the west boundary of Kirtland road with a line from the iron pipe reported to be at the S.W. Corner of Lat "F" of the Whiting tract thru the south reference point for the point of curve, which point was found to be 25.0 southerly from the engineers centerline as monumented. Then established and monumented the required tract being 208.0 feet on four sides and bounded by the said Southern Pacific Company property on the north and the west boundary of Kirtland Road on the east.

June 25, 1952

REGISTERED
OREGON
LAND SURVEYOR

C. Z. Boyden

MARCH 10, 1944
C. Z. BOYDEN

7

