



SCALE :
1" = 100'



SURVEY FOR
SCOTT WICKERSHAM
SEC. 16 T37SRIW
FEB. 1952

REGISTERED
OREGON
LAND SURVEYOR

C. Z. Boyden
MARCH 19 1954
C. Z. BOYDEN
7

Survey No. ~~520~~

For: Scott Wickersham.,

Location: Section 16, Township 37 South, Range 1 West.

Purpose: To establish the boundaries of the Wickersham property and then survey and monument subdivisional tracts as directed.

Procedure: The boundaries of the said property were located according to the description recorded in Jackson County Deed Records, Volume 256, Page 112, with the point of beginning being a record distance East and South from the reestablished corner to Sections 8, 9, 16 and 17. Since this location of the property did not agree with the physical boundaries of the tract as occupied, the point of beginning was moved southerly along the West boundary to an intersection with the fence along the northerly boundary. By request of Mr. Wickersham this fence was used as the northerly boundary of the property for this survey and so monumented.

The location of Roberts Road was established as now located and constructed by order of County Engineer.

By intersecting the northwesterly boundary of Roberts Road with the record west boundary of the property as described and the said above mentioned fence line, the Wickersham property was thus enclosed and the smaller tracts monumented as shown on the map to accompany this report.

Meridian was established by astronomical observation.

REGISTERED
OREGON
LAND SURVEYOR

C. Z. Boyden
MARCH 10, 1944
C. Z. BOYDEN
7

JACKSON
COUNTY
ENGINEER-SURVEYOR
MAY 17 1953