

SURVEY FOR  
HARRIS & MADDEN  
SEC. 9 T38SRIW  
BY: C.Z. BOYDEN  
MAR. 1953



SCALE: 1" = 40'

- IRON PIN
- IRON PIPE
- RE-ESTB'D GOV'T. CORNER

REGISTERED  
OREGON  
LAND SURVEYOR

MARCH 10, 1944  
C. Z. BOYDEN  
7

MADDEN

HARRIS

W.N.W. COR.  
DLC # 44  
E.COR.  
DLC # 41  
(iron pipe)

West  
30.36

Set pin on line

683.25

S 89° 33' 30" E 104.355

S 0° 23' W

N 0° 23' E 178.71

178.71

N 89° 33' 30" W 104.355

Set PI.  
(1/2" iron pipe)

30.0'  
30.0'

HOUSTON ROAD

30.0'  
30.0'

1/4 Sec. Cor.  
Sects 9 & 10

Survey Narrative to comply with Sec. 87-330, Oregon State Law, 1947.

Survey No. 530

For: Guy Harris & E. S. Madden

Purpose: To establish the boundaries of the Harris Property and set a line point on the east line of the Madden Property, being located in Section 9, Township 38 South, Range 1 West, Willamette Meridian.

Procedure:

Established the west boundary of D.L.C. No. 44 from the South one-quarter corner of Section 9, to a hub at the WNW corner of said D.L.C. No. 44, said hub for corner being set a government record distance (30.36 feet) west of the SSE corner of D.L.C. No. 41. Then established the centerline of Houston Road from records filed in the county engineer's office. With these lines as a control, established the boundaries of the Harris Tract and set a point on the east line of the Madden Tract as shown on the map to accompany this report. Reference monuments for the south corners of the Harris Tract were set on the boundary of the county road.

March 25, 1953

REGISTERED  
OREGON  
LAND SURVEYOR

*C. Z. Boyden*

MARCH 10, 1944  
C. Z. BOYDEN.

7

