



Survey Narrative to comply with Section 87-330 Oregon State Law,  
1947.

Survey No. 531

For: C. C. Heard

Location: Section 31, Township 37 South, Range 1 West, Willamette  
Meridian.

Purpose: To establish the boundaries of the Heard property and  
then monument and describe a portion thereof as directed.

Procedure: Established the south and east boundaries of D.L.C.

No. 44 between the officially re-established corners of said claim.

Then established the relocated centerline of the Pacific Highway  
from engineer's centerline station points at 535+32.52 P. & T. and  
542+00 P. O. T. Since the relocated centerline of said highway is  
a parallel offset from the old line the record frontage distances  
of the Heard tract would be unchanged, but since the property is  
described in two parcels which cause a record overlap within the  
property the extreme Southwest and Northwest corners were estab-  
lished at a record intersection with the Easterly right of way  
line of the relocated Highway and the North boundary ran East  
parallel to the South boundary of said D. L. C. No. 44. The  
triangular tract conveyed by Mr. Heard and located in the South-  
east corner of said property was excluded considering the base  
and altitude sides as a control.

Then monumented the boundaries of a parcel in the Northwest corner  
as directed and shown on the map to accompany this report.

April, 1953



