

(No map accompanied this Narrative)

TIMBER ESTIMATES
APPRAISALS - LOGGING PLANS

SURVEY NO. **534**

ROADS - MAPS
ALL TYPES TIMBERLAND SURVEYS

Claude Kerr Cruising and Engineering Service

REGISTERED PROFESSIONAL ENGINEER
Real Estate

PHONE 3.3751 2430 FOOTHILL DRIVE
ROSEBURG, OREGON

Oct. 2, 1952

County Surveyor
Medford, Oregon

Dear Sir:

I recently re-established the following corners in T32S, R1W:

1. 1/4 corner between Sections 12 & 13, T32S, R1W. Found both the original BTs. *size of stone OK.*
Reset the 18"x10"x6" Basalt stone, which had fallen over. A metal tag is on one BT.

2. 1/4 corner between Sections 12 & 7 along east side of T32S, R1W. *Sp-3 500 -*
Corner stone in place. Is 10 feet east of a huge Boulder outcrop. *No reference in orig. note.*
Original R. Fir B. T. is now 26" in diameter. *20" orig.*
Original Laurel is now gone.
New B. T. scribed a 5" Laurel bears N 88° W for 4 feet,
marked WM 1/4 S

3. 1/4 corner between Sections 1 and 12, T32S, R1W.
The original Laurel BT is standing. I chopped off the healed-over wood and found the old face rotten. The 1/4 S BT scribe showed plainly in the healed-over wood which was chopped off. *Laurel NW in orig note*

I scribed two new BTs
A 14" Red Fir bearing N 64° E for 36.3 feet.
marked 1/4 S 1
A 16" Red Fir bearing S 80° E for 27.5 feet
marked 1/4 S 12

Set a stone 8"x12"x16" for 1/4 corner marked 1/4 S on South face

Y Corner for Sections 12, 13, 7, and 18 along east side of T32S, R1W.

Found the original 22" Fir BT bearing (N 60° W for 19 Links.) Scribe plainly visible. *9*
(Is now 33" in diameter)
Original Fir BT bearing N 80° E for 13 Links still stands. Scribe visible.
Other Original BTs are now gone.

Straightened up and reset the stone at the corner.

The NE corner of Sec. 12, T32S, R1W - I chained North from the 1/4 corner for Sections 7 and 12 for 2497 feet to the intersection of the two old blazed lines. This point is 5 chains North of a ravine as called for in the field notes. *OK for ravine*

No BTs are standing, but the remains of three laurels and an oak check very closely to the original notes. *OK for type of BTs*

A 3"x4" Fir post was set at this point and marked for Sections 1 and 12. *Common corner for NW & 1 E.*

Yours very truly,

