

(No map to accompany this Narrative)

Grants Pass, Oregon.
April 27, 1953.

Mr. Paul Rynning,
County Surveyor,
Medford, Oregon.

Dear Sir:

The following are descriptions of corners rehabilitated by me in connection with Mineral Survey No. 910, Oregon;

Township 38 South, Range 2 West, Willamette Mer., Oregon

At Cor. No. 1 of the Kate-El lode, identical with the $\frac{1}{4}$ sec. cor. of secs. 28 and 33,

Set a quartz stone, 24x6x6 ins., 16 ins. in the ground, surrounded by a mound of stone to top, mkd. X on top, $\frac{1}{4}$ on NE., K-E-1-910 on NW. face; from which

A fir, 32 ins. diam., bears N.36 $\frac{1}{2}$ °W., 26.4 ft. dist., an old bearing tree with blaze healed.

A madrona, 18 ins. diam., bears South, 7.92 ft. dist., an old bearing tree mkd. $\frac{1}{4}$ S. BT.

And new bearing trees as follows:

A fir, 30 ins. diam., bears N.89 $\frac{1}{2}$ °W., 34.3 ft. dist., mkd. K-E-1-910 BT.

A black oak, 8 ins. diam., bears N.11 $\frac{1}{2}$ °W., 26.4 ft. dist., mkd. K-E-1-910 BT.

At the point for cor. of secs. 28, 29, 32, and 33,

Set an iron pipe, 60 ins. long, 2 ins. diam., 36 ins. in the ground, mkd. RS33; from which

A yellow pine stub, 32 ins. diam., bears N.29°E., 164.1 ft. dist., with partial scribe marks on charred face of old blaze. (Old B.T.)

A white oak, 26 ins. diam., bears S.89 $\frac{3}{4}$ °E., 285.8 ft. dist., with blaze healed. (Old B.T.)

A black oak, 30 ins. diam., dead and down, bears N.58°W., 178 ft. dist., with old blaze decayed. (Old B.T.)

A yellow pine, 6 ins. diam., bears N.85 $\frac{1}{2}$ °E., 46.9 ft. dist., mkd. T38S R2W S28 RS33 BT. (New B.T.)

A fir, 14 ins. diam., bears S.27 $\frac{1}{2}$ °W., 37 ft. dist., mkd. T38S R2 W S32 RS33 BT. (New B.T.)

A yellow pine, 22 ins. diam., bears N.50 $\frac{1}{2}$ °W., 15.6 ft. dist., mkd. T38S R2W S29 RS33 BT.

