

(No map accompanied this Narrative)

County Surveyor,
Jackson County,
Medford, Oregon.

Dear Sir:

The following sec. cor. was rehabilitated by me in connection with a preliminary survey of the Yellow Baby Lode Mining Claim of George E. Cockman, Sr.

The locus of the cor. of secs. 19, 24, 25, and 30, on E. bdy. of T. 38 S., R. 5 W., Willamette Meridian, Oregon, is determined at the record distances from the original SE. and SW. bearing trees;

At the corner point,

Set an iron pipe, 3 ft. long, 2 ins. diam., 28 ins. in the ground, mkd. RS33; from which the original bearing trees

A sawed fir stump, 16 ins. diam., bears S.77½°E., 77 lks. dist., mkd. R4 T38 S30 BT.

A Douglas fir, 48 ins. diam., bears S.16½°W., 10 lks. dist., with blaze healed.

And new bearing trees

A Douglas fir, 20 ins. diam., bears N.81°E., 58 lks. dist., mkd. T38S R4W S19 RS33 BT.

A Douglas fir, 14 ins. diam., bears S.69°E., 47 lks. dist., mkd. T38S R4W S30 RS33 BT.

A Douglas fir, 6 ins. diam., bears N.20°W., 49 lks. dist., mkd. T38S R5W S24 RS33 BT.

Grants Pass, Oregon.
May 22, 1953.

CC to County Surveyor,
Josephine County,
Grants Pass, Oregon.

REGISTERED
OREGON
LAND SURVEYOR

Norman D. Price

JULY 7, 1944
NORMAN D. PRICE
No. 33

