



OREGON
 LAND SURVEYOR
Lester E. Smith
 LESTER E. SMITH
 254

MAP of SURVEY
 for
 J. A. & Lela Larimore
 To Locate Property and Parcel
 Lines as Shown
 June 1953
 Not to Scale

Survey Narrative to Comply with Section 87-330, 1947 Oregon State Laws.

Survey for: J. A. and Lela Larimore

Location: Section 13, Donation Land Claim No. 59 in Township 37 South, Range 2 West, Willamette Meridian, Jackson County, Oregon.

Purpose of Survey:

To determine and monument the exterior boundaries and two subdivisional lines of the property described in Jackson County Deed Records, Volume 356, page 159 and Volume 60, page 419.

Procedure: Found the southwest corner of said D.L.C. No. 59 according to call of the Jackson County Surveyor's records.

Found a point on the west line of D.L.C. 59, 2208.36 feet north of said southwest corner of D.L.C.No. 59 according to call of surveys of record in the Jackson County Surveyor's office.

Found lot corners of Mace Subdivision, as surveyed and set by Leland Lovejoy, as of record in Jackson County Surveyor's office.

Search for the initial point of the Mace Subdivision showed the location to be under the roots and base of a large ornamental tree, at which point a stone was determined by probing with an iron bar.

All determinations on the ground agree with the records except the north and south distances shown in said Deed Record Volume 356, page 159. However, a thorough search of the Deed Records, particularly Volume 60, page 419 show the true situate of the subject property. I, therefore, surveyed and established the lines and monuments as shown on the accompanying map.

Lester E. Smith
June 1953

