



**BOUNDARY LOCATION
PROPERTY SITUATE IN**

**D L G 37 T 37 S R 2 West 1/4 W 1/4
JACKSON COUNTY, ORE.**

**J. H. CLABBY
SEAFORD, OREGON**

**CIVIL ENGINEER
9 FEB. 1953**

SCALE 1" = 50'



Survey Narrative to Comply with Section 87-330, 1947 Oregon State Laws.

Survey for: H. F. McLaughlin

Sections 29 and 32

Location: D.L.C. 37, Township 37 South, Range 2 West, Willamette Meridian,
Jackson County, Oregon

Purpose of Survey:

To survey two lots as designated on the ground by owner.

Procedure:

Found Northeast corner of D.L.C. 37, also points on North and East lines which were established on previous surveys.

Vicory - From D.L.C. corner ran west 194.60 feet to an iron pipe for point of beginning, thence continued West 172.22 feet, thence South $5^{\circ} 15'$ East 335.20 feet, thence North $55^{\circ} 11'$ East 172.37 feet, thence North 235.41 feet to the point of beginning.

Tuttle - From D.L.C. corner ran west 366.82 feet to an iron pipe for true point of beginning, thence continued west 79.00 feet, thence south 322.72 feet, thence South $58^{\circ} 58'$ East 87.78 feet, thence north 10.00 feet, thence North $55^{\circ} 11'$ East 42.00 feet, thence North $5^{\circ} 15'$ West 335.20 feet to the point of beginning.

J. H. Clabby

February, 1953

