

Survey Narrative to Comply with Section 87-330, Oregon State Law
(1947)

Survey For: P. J. HOFFMAN et al

Purpose: (1) To monument and describe a tract of land within the Ferrell (DR 358-382) and Hoffman (DR 284-628) Properties as directed, for the purpose of deed-ing to a third party.

(2) To monument and describe a new boundary between the Hoffman and Jerome properties, as directed.

Procedure: Commenced at the official re-established S.S.E. corner D.L.C. #48, T 37 South Range 2 West, and ran westerly in search of several iron pipes called for in the Jerome and Hoffman Deeds. Found the monuments for the P. O. B. and the Northwest corner of the Hoffman property only.

From the said D.L.C. Corner and on line with the said Northwest corner of the Hoffman property ran deed record distance Westerly to establish the Southeast corner of the Ferrell property, also being a corner of the Hoffman property, where an iron pin was set.


Established the centerline of the Old Stage Road from monuments found on the Northeasterly boundary of said road as set on a previous survey from this office in 1940.

Then from the iron pipe found for the P. O. B. of the Hoffman property ran said established road bearing a deed record distance Northwesterly to a point on line between the Hoffman and Ferrell properties.

Then monumented the tract and the new division line between Jerome and Hoffman properties, setting iron pins on said established road boundary.

November, 1953

Working on field



Mark E. Boyden

