

Township 34 South, Range 4 West, Willamette Mer., Oregon  
Rehabilitation of Cor. of Secs. 9, 10, 15, and 16.

The locus of cor. of secs. 9, 10, 15, and 16 is determined at the record bearing and distance from each of the original bearing trees.

At the corner point,

Set an iron pipe, 3 ft. long, 2 ins. diam., 28 ins. in the ground, mkd. RS33; from which the original bearing trees:

A sawed incense cedar stump, 36 ins. diam., bears N.59°E., 50 lks. dist., with axe marks remaining.

A black oak, 12 ins. diam., bears S.30°E., 77 lks. dist., with old blaze uncovered and decayed.

A sawed yellow pine stump, 44 ins. diam., bears S.42°W., 150 lks. dist., on which partial scribe marks remain.

A black oak, 12 ins. diam., bears N.66°W., 44 lks. dist., with old blaze uncovered and decayed.

And new bearing trees as follows:

A madrona, 6 ins. diam., bears N.38°E., 60 lks. dist., mkd. on bark T34S R4W S10 RS33 BT.

A Douglas fir, 8 ins. diam., bears S.31½°E., 49 lks. dist., mkd. T34S R4W S15 RS33 BT.

A Douglas fir, 6 ins. diam., bears S.30°W., 85 lks. dist., mkd. T34S R4W S16 RS33 BT.

A madrona, 8 ins. diam., bears N.55°W., 17 lks. dist., mkd. on bark T34S R4W S9 RS33 BT.

An unmarked iron pipe, 3/4 in. diam., 4 ins. above ground, firmly set, bears N.20°W., 2½ lks. dist.

The above described corner was rehabilitated by me at the request of Grasser Bros., whose P. O. address is Box 1247, Roseburg, Oregon, on November 20, 1953.

I hereby certify that the above described rehabilitation of cor. of secs. 9, 10, 15, and 16, T. 34 S., R. 4 W., Willamette Meridian, Oregon, was executed in conformity with the Laws of the United States and the Laws of the State of Oregon.

November 20, 1953,  
Grants Pass, Oregon.

CC to  
Gasser Bros.  
U. S. Dept. Interior, B. of L. M.  
Original mailed to County Surveyor,  
Jackson County, Medford, Oregon.

*Norman D. Price*  
Norman D. Price,  
Registered Professional  
Land Surveyor for Oregon,  
No. 33.

