



BOUNDARY LOCATION
 Property Situate in
 Sec. 32, Twp. 32 S, R. 3 E, W. M
 JACKSON COUNTY, OREGON
 J. H. CLABBY CIVIL ENGINEER
 Medford, Oregon Sept. 1954

SCALE: 1" = 60'

SURVEY from record



Survey Narrative to Comply with Section 87-330, 1947 Oregon Law.

Survey for: William Mooney

Location: Section 32, Township 32 South, Range 3 East, Willamette Meridian
in Jackson County, Oregon.

Purpose of survey:

To survey and divide a parcel of land recorded under Deed Record
313-21.

Procedure: Found quarter corner common to Sections 29 and 32 and the northeast
corner Section 32. Located the northeast corner of the Northeast
quarter of the Northwest quarter of the Northeast quarter of Section
32 at a point on section line and 1325.96 feet west of said Northeast
corner of Section 32. Continued west 445.50 feet for the true point of
beginning, thence South 404.25 feet, thence west 214.50 feet, thence
North 404.25 feet, thence East 214.50 feet to the point of beginning.

Pipe monuments were also set at the intermediate points on east and
west boundary lines.

Fences on the east and west are some 6 feet west of the lines established
by survey. The south fence is 6 feet south of the survey.

The owner was advised that a comprehensive survey of his property will
entail the subdivision of Section 32 which, for the most, part lies
in difficult terrain. He was further advised that future surveys may
change the bearings for the east and west lines.

J. H. Clabby

October 1954

