



BOUNDARY LOCATION
Property Situate in
D.L.C. 40, T.38 S., R.2 W. W.M.
JACKSON COUNTY, OREGON
J. H. CLABBY CIVIL ENGINEER
Medford, Oregon Oct. 1954
SCALE; 1" = 50'



Survey Narrative to Comply with Section 87-330, 1947 Oregon Law.

Survey for: Daniel Chisholm

Location: D. L. C. 40, Township 38South, Range 2 West, Willamette Meridian,
Jackson County, Oregon.

Purpose of Survey:

To survey the parcel of land occupied by a gasoline service station and recorded in the Records of Jackson County, Oregon.

Procedure: Established east line of D. L. C. 40, said township and range. Found northeast corner Lot 1, Block 3, and northwest corner Lot 2, Block 1 of the Britton Subdivision as recorded in the records of Jackson County, Oregon. From these points I established intersection of Stage Road with east line of D.L.C. 40. From said intersection ran North 30.69 feet, thence North $76^{\circ} 15'$ West 20.6 feet for the true point of beginning, thence continue North $76^{\circ} 15'$ West 98.20 feet, thence North 183.61 feet, thence South $76^{\circ} 15'$ East 98.20 feet, thence South 183.61 feet to the point of beginning.

J. H. Clabby

October 1954.

