

Survey Narrative to Comply with Paragraph 209.250 Oregon Revised Statutes.

Survey For: GEORGE BELLAH

Purpose: To survey that portion of the Northeast $\frac{1}{4}$ of the Southwest $\frac{1}{4}$ of Section 6, Township 38 South, Range 2 West, now owned by Mr. Bellah. Also to survey and prepare descriptions for 3 tracts therein now on contract for sale.

The center of said Section 6 had been set and referenced by County Surveyor G. Elksnat on or about 1896. The county surveyor's office has since in the year of 1934 reestablished the Southwest corner, West $\frac{1}{4}$ corner and South $\frac{1}{4}$ corner of said Section and established the center South 1/16 using the center of Section as set by Mr. Elksnat. The South 1/16 corner between Sections 1 and 6 was established at the time of the 1934 survey.


From these re-established and established corners, the boundaries of the said Northeast $\frac{1}{4}$ of the Southwest $\frac{1}{4}$ were determined by a proportional division of the North $\frac{1}{2}$ of said Southwest $\frac{1}{4}$.

Since Mr. Bellah owned that portion Southeast of the old Applegate County Road, and the Sterling Road was to divide tracts to be deeded, the location of these roads was established under the direction of the county engineer.


The remaining divisional lines were established as directed by Mr. Bellah.

The length and bearing of all lines and monuments set or found are indicated on the map to accompany this report.

Meridian was determined by solar observation.



June - 1954



Mark E. Boyden

