



Survey Narrative to comply with Paragraph 209.250,  
Oregon Revised Statutes.

FOR: George Moore

PURPOSE: To monument the outside boundary of the Moore property as described in Jackson County Deed Records, Volume 290, Page 170, and to monument and describe five parcels as directed, being located in Section 20, Township 37 South, Range 1 West.

PROCEDURE: The point of commencing, the 1/4 Section corner monument to Sections 17 and 20 was recently dug out by water line construction. Was able to replace same from three accurate reference points (See Re-establishment 1953) and set a 1" x 36" galvanized iron pipe monument for corner.



Found the remainder of Sectional control monuments from references reported in the Re-established and Established Records, County Surveyor's Office, and the location lines of Buckshot and Springbrook Roads from the County Road Records.

Established the North and West boundaries of the Moore property according to the Deed Records.

Meridian control on the North-South centerline of Section 20, as previously determined by this office on the Nichols Estate Survey (Survey No. 314), was used on this survey.

A description was prepared for that portion of the Moore property lying within the County Roads, for the purpose of deeding said property to Jackson County.

October 1955.



*Mark E. Boyden*  
NOVEMBER 6, 1951  
MARK E. BOYDEN  
281