

Edward A. McGinty, L.S.  
103 King Street  
Medford, Oregon

April 9, 1956

Paul Rynning, County Surveyor  
Jackson County Court House  
Medford, Oregon

Subject: Restoration of obliterated corner.

T. 38 S., R. 2 W., W.M.

1/4 corner section 8 and 9.

Found small rock mound at corner which I set 1 inch by 6 foot iron pipe,  
4.5 feet in the ground. Orig. 4 inch laurel, now a 16 inch stump BT  
visible bears South 40° East, 43 links.  
Orig. 18 inch fir remains, only bears South 35° West 33 links.  
New double blazed 16 inch fir bears North 20 1/2° West 84.8 links.  
New double blazed 8 inch fir bears South 82° West, 55 links.

REGISTERED  
OREGON  
LAND SURVEYOR

*Edward A. McGinty*

JULY 10, 1953  
EDWARD A. MCGINTY  
301

