



F.D. S.W. COR.  
MACE SUB'D.

S.L. MACE SUB'D.

1" PIPE F.D.

S.L. MACE SUB'D.

N 89° 58' 30" E

181.66 NL DEED

11.09'

F.D. PIN

F.D. PIN

560.01

N 0° 01' 30" W

S 0° 01' 30" E. 560.37

181.66'

S 89° 54' 45" E

419.60

0.15'

992.62'  
991.75'

HOWARD ST.

W.L. - D.L.C. 59 N 0° 01' 30" W 1564.28 (R. = 1565.6')

SURVEY IN D.L.C. 59 T. 37 S. R. 2 W. W. M.  
FOR

HOWARD SCHOOL &  
E. MC INTIRE

BY EDW. MC GINTY  
MEDFORD, OREG.

SCALE 1" = 100  
MAY, 1956

1. BOLT  
DEBARR  
S 89° 54' 45" E  
S.W. COR  
D.L.C. 59  
N.W. D.L.C. 60

RECORDED  
ORIGIN  
LAND  
MAY 1956  
Edward L. Mc Ginty

Survey Narrative to comply with O.R.S. 209-205 and O.R.S. 209-120

Survey for: E. E. McIntire & Howard School

By: Edward A. McGinty

BASIS OF BEARING:

*Sec. 13  
D.L.C. 59, T. 37S., R. 2W.*

Surveys of record which complies with OSL

PRECEDENCE OF SURVEY:

To determine boundaries of second portion described in deeds of record Vol. 390 page 483.

The southwest corner of DLC 59, a hex pin 10 inches deep was found, also the northwest corner DLC 60 a hex pin 12 inches deep from which I set a 1/2 inch Iron pin North 0°12' West: 20.00 feet. Found 1 inch Iron pipe at the southwest corner Mace sub-division corner being pt accepted as being on the west line of DLC 59 (reference: see narrative of surveys of record No. 582) Also found old rusted 1 1/4 inch Iron pipe 8 inches deep 0.54 south and 0.35 feet west of southwest corner of Mace sub-division.

In this survey, the exact south line of Mace Sub-division was not determined as deeds of records on surveyed property fell south of Mace sub-division.

Set 3/4 inch Iron pipes as shown on map of surveyed parcel. The south line of parcel deed adjacent, east line deed adjacent, and west line deed adjacent, north line deed of record of surveyed parcel.

