



PROPERTY MAP
 Leland J. Knox
 Section 27, T. 375 R. 1 W.
 Jackson County, Oregon.
 Apr. 15, 1956 Hugh C. Ingle
 Scale 1" = 200' Civil Engineer



NARRATIVE REPORTSURVEYPortion of N. W. $\frac{1}{4}$ of Section 27Township 37 South, Range 1 West W.M.For: *Leland J. Knox*Purpose of Survey.

This survey was made for locating outside boundaries of Tracts A and B and making descriptions thereof.

Procedure.

The re-established corners at the Northeast and Northwest corners of Section 15 were found and the line was run between them and chained West from the Northeast corner. The quarter corner was not found but a check from a bearing tree by distance and bearing tie agreed with the half way distance.

The west boundary was run south from the section corner to a point on the north line of D.L.C. # 59 at record distance of description west of the found Northeast corner of D. L. C. # 59; line then run south on East line of D. L. C. # 59 to North line of D. L. C. # 58; thence East on North line of D. L. C. # 58 to found Northeast corner of D.L.C. # 58 and corner for property placed at record distance; thence North on record bearing to the beginning point of property description on section line thence West on section line to Northwest corner of Section.

The southeast corner of the tract was found to be 6.4 feet West of record distance for corner described for tract bordering on East of surveyed land.

