

Edward A. McGinty, L.S.
105 King Street
Medford, Oregon

May 28, 1956

Paul Kynning, County Surveyor
Jackson County Court House
Medford, Oregon

Subject: Re-established Section Corner

Township 37 South, Range 1 West

1/4 corner Sec. 7 and 8

Original notes called for raised mound considered lost for many years. Since there has been no legally recognized corner of record, the reestablished was set with a 5/8 inch pin 1 inch below surface at a proportional distance, according to law.


Collateral evidence of said location, fence line to East. From said 1/4 corner.

Center 10 inch Poplar	bears	North 44 1/2° East	59.8 feet
Center Tel. pole	bears	South 61 1/4° East	34.0 feet
Center Power pole	bears	South 18 1/4° East	93.0 feet

South 1/16 corner of section 7 and 8

Set a proportional distance a 5/8 inch Iron pin 1 inch below surface near center of Grater Lake Ave. from which bears,

Center tel. pole No. 89	South 37° East	50.41 feet
Center Power pole No. 2233	North 37° West	52.45 feet



Edward A. McGinty

