



**BOUNDARY LOCATION**  
**LOTS 27 & 28**  
**AMERICAN ORCHARD TRACTS**  
**Sec. 32, Twp. 36 S., R. 1 W., W. M.**  
**JACKSON CO., OREGON**  
**J. H. GLABBY, C.E. JULY, 1956**  
**SCALE: 1" = 100'**

Survey Narrative to Comply with Section 87-330, 1947 Oregon State Laws.

Survey for: H. S. Cummings

Location: Section 32, Township 36 South, Range 1 West, W.M., Jackson County, Oregon, (Lots Nos. 27 and 28 American Orchard Tracts).

Purpose of survey:

To locate northwest and southwest corners of Lot No. 28 and the northeast and southeast corners of Lot No. 27.

Procedure: The plat of the American Orchard Tracts shows point of beginning and the Quarter (1/4) corner common to Sections 31 and 32. This corner could not be found. The Northwest and the southwest corners were located and the chained distance between was found to be 5303.80 feet. The Quarter (1/4) corner was taken as the midway point 2651.80 feet south from the northwest corner of Section 32.

From midway point set  $\frac{1}{2}$ " iron pin 30 feet east of section line on right of way line of old Crater Lake Highway. Found corner set for Warren C. Bayliss, September 1952.

From iron pin foresight on Bayliss corner ran South  $89^{\circ} 35'$  East 750.4 feet and set corner, thence North 581.10 feet and thence North  $89^{\circ} 35'$  West 750.4 feet.

July 1956

J. H. Clabby

