



REGISTERED
OREGON
LAND SURVEYOR
L. E. AGER
MARCH 10, 1946

DETAIL-MAP

Survey for Gordon Green, Stagecoach Cr.
In Donation Land Claim #44
T. 38 S. R. 2 W. W. 1/4, Oregon.
Survey Completed Feb. 4, 1950 By L. E. Ager
Bearings taken by Solar Ob. Scale: 1" = 100'

S.M. COR. D.L.C. 44
T. 38 S. R. 2 W. W. 1/4
1/2" Iron Pipe Witness Three
Reestablished by Co. Surveyor

S.E. COR. D.L.C. 44, T. 38 S. R. 2 W. W. 1/4
1/2" Iron Pipe Witness Three
Reestablished by Co. Surveyor

MEASURED DIST. BEARING: S. 89° 48' E. 747.08
S. 89° 48' E. 763.22

(GOV. FIELD NOTES N. 91° 15' E. 6541.67)
(S.E. COR. D.L.C. 44) 1/2" IRON PIPE WITNESS THREE

Survey narrative to comply with Section 87 - 330, Oregon State Law of 1947.

For: Gordon Green, Medford, Oregon

Purpose: To stake and describe the boundaries of tracts of land located in Donation Land Claim No. 111, T. 38 S. R. 2 W. W.M., Jackson County, Oregon.

Procedure:

Sec. 4
Began at an iron pipe at the southeast corner of said Claim which was set by the Jackson County Surveyor on reestablishment of this corner and ran a random line West toward the southwest corner of said Claim. At a point 6541.67 West and 22.83 feet North of the Southeast corner I found an iron pipe which was originally set for the southwest corner of this Claim. (The original field notes read N. 89° 48' E. 98.35 chains or 6491.10 feet between these corners.). From hubs set at chained intervals along the random line I offset from this computed distances and set iron pipes on true line at points of this survey as indicated on the accompanying map. From these points on the south line of this claim I proceeded to survey the boundaries of the tracts as shown on the accompanying map according to the bearings and distances shown thereon.

