



REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
Lloyd R. Moffit
 OREGON
 JULY 17, 1970
 LOYD R. MOFFIT
 944

** RECEIVED **
 Date *7/9/84* By *SK*
 This survey consists of:
 / sheet(s) Map
 / page(s) Narrative
 JACKSON COUNTY
 SURVEYOR

LEGEND:
 ● = FOUND 1972 B.L.M. BRASS CAP MARKING THE SECTION CORNER.
 ○ = SET 5/8" IRON PIN WITH PLASTIC CAP STAMPED, MOFFIT PLS 944.
 — = PROPERTY LINE MARKED WITH LATH AND FLAGGING.
BASIS OF BEARINGS:
 ORIGINAL GOVERNMENT SURVEY BEARING ON THE EAST LINE OF SECTION 3.

PLAT OF SURVEY
 FOR
LOUISIANA-PACIFIC CORP.
 BEING A PORTION OF SECTION 3, TOWNSHIP 37 SOUTH, RANGE 1 EAST, WILLAMETTE MERIDIAN, JACKSON CO. SCALE: 1"=400'
 OREGON DATE: JUNE, 1984
 PREPARED BY: FRIAR - MOFFIT AND ASSOCIATES
 MEDFORD, OREGON

SURVEY NO. 10011

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: LOUISIANA-PACIFIC CORP.
P.O. BOX 711
LAKEVIEW, OR 97630

LOCATION: SECTION 3, TOWNSHIP 37 SOUTH, RANGE 1 EAST,
WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON.

PURPOSE: TO SURVEY AND MARK PROPERTY LINES AS SHOWN ON
THE ATTACHED MAP.

PROCEDURE: A TRAVERSE WAS RAN AROUND THE EXTERIOR OF SECTION
3. ALL CORNERS THAT WERE NEEDED FOR THIS SURVEY
WERE FOUND EXCEPT THE WEST ONE-QUARTER CORNER.
AT SAID CORNER I FOUND A 22 INCH WHITE OAK WHICH
HAD BEEN CUT INTO MANY YEARS AGO. THE INSIDE OF
SAID OAK HAD ROTTED OUT. IT SHOULD BE NOTED THAT
THE ORIGINAL NOTES CALL THIS OAK A BLACK OAK.
USING A STAFF COMPASS, I WENT RECORD S27°W 61
LINKS (40.26') FROM SAID OAK. FROM THIS LOCATION
I FOUND THE ROOT HOLE OF A DOWN AND ROTTING 16
INCH OAK WITH VERY OLD AXE MARKS AT APPROXIMATELY
N64°W 46 LINKS (30.36'). THEREFORE I SET A 5/8"
PIN AT THE RECORD DISTANCE FROM THE 22 INCH OAK.
FROM THE ONE-QUARTER CORNER BETWEEN SECTIONS 2
AND 3 A NEW 5 INCH OAK BEARING TREE BEARS S39°
16.18 FEET, SCRIBED 1/4 S2 BT.

AT THE CENTER ONE-QUARTER OF SECTION 3 I SET A
5/8" IRON PIN FROM WHICH:

A 12 INCH OAK BEARS S86° W 44.45' SCRIBED
C1/4 S3 BT.

AN 8 INCH OAK BEARS N21° W 20.96' SCRIBED
C1/4 S3 BT.

DATE: JULY, 1984

