



BASIS OF BEARINGS: R.S. 6977

**** RECEIVED ****
 Date: 7/18/84 By: BYSK
 This survey consists of:
 - 1 sheet(s) Map
 - 1 page(s) Narrative
 JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
Darrel W. Edwards
 OREGON JULY 9, 1958
 DARREL W. EDWARDS
 741

SURVEY FOR: CECIL ROBERTS		
SCALE: 1" = 300'	● Monument found as noted	DRAWN BY <i>Bae</i>
DATE: MAY 15, 1984	○ 5/8" x 24" steel pin set	REVISED
LOCATION: In the Thomas Whitworth D.L.C. No. 51 in the NW 1/4, Sec. 18, T. 38 S., R. 1 W., W.M. in Jackson County, Oregon		
() Record Measurement	DRAWING NUMBER	
x-x-x Fence Line		

SURVEY NO. 10016

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250, OREGON REVISED STATUTES.

SURVEY FOR: Cecil Roberts
2076 Roberts Rd.
Medford, OR. 97501

LOCATION: In the Thomas Whitworth D.L.C. No. 51 in the NW 1/4,
Section 18, T. 38 S., R. 1 W., W.M. in Jackson County,
Oregon.

PURPOSE: To locate and monument the property boundaries of Mr.
Roberts' parcel.

PROCEDURE: I first traverse to and tie in the South and East 1/4
Corners and the SE Corner of Section 18. I then trav-
erse from the NW Corner to the NE Corner of D.L.C.
No. 51.

A thorough search was made for the North 1/4
Corner and the NE Corner to no avail. Cost being pro-
hibitive, it was not possible to re-establish these
Corners. Using information from R.S. 6977 and original
Gov't. survey records, I calculated the position of
these Corners, the Corners of Gov't. Lot 4 and the
Corners of Mr. Roberts' parcel. I then traverse
around the parcel and set 5/8" x 24" steel pins with
a plastic cap stamped "DW EDWARDS-LS 741" as shown on
the accompanying plat.

EQUIPMENT: Lietz TM-20C theodolite and Lietz RED-1 EDM.

BASIS OF
BEARINGS: R.S. 6977

DATE
COMPLETED: May 15, 1984

EDWARDS SURVEYING
P. O. Box 201
Rogue River, OR 97537
Phone 532-3110

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Darrel W. Edwards

OREGON
JULY 8, 1966
DARREL W. EDWARDS
741

