



REGISTERED
PROFESSIONAL
LAND SURVEYOR
Robert M. Thompson
OREGON
ROBERT M. THOMPSON
1958

RECEIVED
Date: 8/16/84
This survey complies with the provisions of the Oregon Revised Statutes, Chapter 310, Section 005, and the rules of the Board of Professional Land Surveyors, Oregon.

LEGEND & NOTES:
 BEARING BASIS: SURVEY NO. 4734 REC. FOR W/2 OF SEC. LINE BET. SECS. 2 & 11
 SEE SEPARATE NARRATIVE FOR CORNER INFORMATION.
 THIS SURVEY & MAP WAS COMPLETED FOR THE EXCLUSIVE USE OF BOISE CASCADE CORP.
 AND T & L INC.
 ○ OR ⊙ FOUND CORNER.
 ● OR ⊙ SET CORNER, 5/8" X 30" I. ROD W/YEL CAP MKD "THOMPSON";
 — LINE MARKED W/RED-PAINTED BLAZES & FLAGGING, & BCC ALUM. AND/OR
 T & L PLASTIC TAGS, AS APPROPRIATE.

SURVEY TO SET & MARK CERTAIN CORNERS & BOUNDARIES FOR BOISE CASCADE CORP., T & L INC.

IN SECTIONS 10, 11, 12, 14, 15, T 34 S, R 2 W, W. M.
 JACKSON CO., OREGON

AUGUST 1, 1984 SCALE: 1 INCH = 500 FEET

BY ROBT. M. THOMPSON & ASSOC, 1140 ACACIA LN., GRANTS PASS, OR. 97527

SURVEY TO SET & MARK CERTAIN CORNERS & BOUNDARIES FOR
BOISE CASCADE CORP., T & L, INC., IN SECTIONS
10, 11, 12, 14, 15, T34S, R2W, W.M.
JACKSON CO., OREGON

Narrative Description to comply with Par. 209.250, O.R.S.
(Note: 1 map sheet accompanies this narrative)

For: Boise Cascade Corp., Timber & Wood Prod. Group, P.O. Box 100, Medford,
OR. 97501, and T & L, Inc., P.O. Box 269, Springfield, OR. 97477

By: Robert M. Thompson & Assoc., 1140 Acacia Ln., Grants Pass, OR. 97527

Purpose: As stated above

Procedure: Copies of all pertinent available information, i.e. U.S. General Land Office (G.L.O.) original field notes, Jackson County and Bureau of Land Management (B.L.M.) corner re-establishments, and Survey Nos. 2977, 4734 and 6530 (Jackson County Surveyor File) were studied for useable information. The original G.L.O. Surveys had been performed by David P. Thompson in 1857, except for the East line of Section 12 by Ives & Hyde in 1854.

All Government corners that could be found were tied in by E.D.M. control survey methods, using Kern one-second and twenty-second Theodolites, K&E Autoranger II E.D.M. equipment, supplemented by steel tape. After office computations and preliminary mapping, the required new corners were set and the specified boundaries were surveyed and marked. Boundaries were marked with red-painted blazes, red flagging, aluminum "P/L BCC" and/or plastic "T&L Property Line" tags, as appropriate to the ownership (note "BCC" and "T&L" designations on my map.) Monuments used for corners set were 5/8"x 30" Iron Rods with a yellow plastic cap marked "Thompson PLS 1358". Corners found or set are as follows:

Original G.L.O. bearing trees (O.B.T.'s) were measured to the "face" position, and newer brg. trees were measured to the center, unless stated otherwise:

Corner Sections 2,3,10,11 found Survey #4734 1" G.I. Pipe w/reducer, and B.T.'s., all w/healed faces:

- 24" D. Fir N 32½°E 19.9' (rec. 19.3' to face)
- 10" D. Fir S 9°E 40.4'
- 12" D. Fir S 74°W 37.7' (rec. 37.5' to face)
- 12" P. Pine N 67°W 51.3' (rec. 51.0' to face)

West 1/16 Cor. Secs. 2 & 11 found Survey #4734 1" G.I. Pipe w/reducer, and B.T.'s. w/healed faces:

- 22" D. Fir N 16°W 32.6' (rec. 31.4' to face) a high cut stump
- 16" P. Pine S 50°W 36.1', a high cut stump

¼ Cor. Secs. 2 & 11 found B.L.M. 1963 br. cap on 2" G.I. Pipe, and B.T.'s.:

- 39" B. Oak N 20°E 13.2', O.B.T., healed, rotted face
- 24" B. Oak S 70°W 24.4', O.B.T., healed, down & dead
- 10" D. Fir N 72°W 16.7' (rec. 17.2') healed, 1963
- 16" D. Fir S 40°E 22.4', healed, 1963

Cor. Secs. 1,2,11,12 found B.L.M. 1963 br. cap on 2" G.I. Pipe and B.T.'s.: (1963 except O.B.T.'s)

- 24" B. Oak S 31½°E 19.8', O.B.T. rotted
- 39" Madrone S 72½°W 43.6', O.B.T., faint scribe vis.
- 20" B. Oak N 46°W 12.5', O.B.T., rotted stump
- 12" D. Fir N 75°E 16.2', healed, 1963
- 16" D. Fir S 42°E 50.8', healed, 1963
- 21" S. Pine S 62°W 86.1', healed, 1963
- 10" B. Oak N 7°W 42.9', healed, 1963

¼ Cor. Secs. 11 & 12 found Survey #2877 1" G.I. Pipe w/reducer and B.T.'s.: (1965 except O.B.T.'s)

- 20" W. Oak S 77°E 19.8', O.B.T. stump, dim scribe vis.
- 14" S. Pine N 76°W 10.6', healed
- 19" D. Fir N 22°E 42.5', healed

Cor. Secs. 11,12,13,14 found B.L.M. 1963 br. cap on 2" G.I. Pipe and B.T.'s.: (1963 except O.B.T.'s)

- 16" B. Oak S 16°W 8.6', O.B.T., down, dead, rotted
- 13" D. Fir N 15°E 54.8' (rec. 55.4'), healed
- 17" D. Fir S 20½°E 108.9', healed
- 23" B. Oak S 70½°W 51.1' (rec. 50.2'), healed
- 11" D. Fir N 27½°W 23.8', healed

¼ Cor. Secs. 11 & 14 found Co. Surveyor 1976 br. cap on 1" G.I. Pipe & B.T.'s.: (1976 except O.B.T.'s)

- 37" D. Fir S 30°W 29.04', O.B.T., "BT" scr. part vis.
- 20" D. Fir N 31½°E 15.9', healed
- 13" W. Fir West 53.1', healed

Cor. Secs. 10,11,14, 15 not found. I set by double propor. meas. 5/8" I. Rod, scribe B.T.'s. "T_R_S_1358 BT":

- 9" D. Fir N 53°W 12.6'
- 9" D. Fir N 17°E 13.8'
- 9" W. Oak S 85½°E 16.5'
- 8" D. Fir S 9°E 27.4'
- 12" D. Fir S 79°E 14.8'

¼ Cor. Secs. 10 & 11 found B.L.M. 1963 br. cap on 2" G.I. Pipe, and B.T.'s.: (1963 except O.B.T.'s)

- 18" B. Oak N 12°W 23.1', O.B.T., snag w/axe marks
- 17" D. Fir S 24½°E 39.6', healed
- 23" B. Oak N 40°W 19.4' (rec. 19.1') healed, face invis.

NW 1/16 Cor. Sec. 11 set 5/8" I. Rod, scribe "NW 1/16S 11 1358 BT" on:

- 8" D. Fir N 46°W 46.4'
- 9" I. Cedar N 70½°E 21.9'

CN 1/16 Cor. Sec. 11 set 5/8" I. Rod, scribe "CN 1/16S 11 1358 BT" on:

- 10" D. Fir N 77°W 8.9'
- 9" D. Fir S 26°W 8.6'

Ctr. ¼ Cor. Sec. 11 set 5/8" I. Rod, scribe "C ¼S 11 1358 BT" on:

- 7" I. Cedar N 36°W 28.8'
- 7" W. Fir S 58°W 17.7'

CW 1/16 Cor. Sec. 11 set 5/8" I, Rod. scribe "CW 1/16S 11 1358 BT" on:

- 7" D. Fir N 39½°E 11.2'
- 7" I. Cedar S 74½°E 16.7'

NE Cor. Sec. 12 found B.L.M. 1963 brass cap on 2" G.I. Pipe, and B.T.'s.: (1963 except O.B.T.'s and Co. Surv. B.T.'s)

- 24" D. Fir N 88°E 18.8' O.B.T., (rec. 18.5'), a stub
- 28" I. Cedar S 56°W 46.9', O.B.T., scribe vis.
- 38" Y. Pine N 68°W 15.2', O.B.T. rotted, burnt stump
- 15" D. Fir S 20½°W 85.1', healed, 1963
- 12" D. Fir N 11°W 12.4' scribe part vis., unrec. B.L.M. 8/82
- 10" Y. Pine N 35½°E 10.6', to face, healed, Co. Surv. BT
- 9" S. Pine S 68°E 7.3' to face, scr. pt. vis., Co. Surv. BT
- 17" W. Oak S 3°W 14.9' to face, healed, Co. Surv. BT

East ¼ Cor. Sec. 12 found Co. Surveyor 1975 brass cap on 1" G.I. Pipe and B.T.'s.: (1975 except O.B.T.'s)

- W'ly Fork of dbl. 14" B. Oak S 60°E 18.5', O.B.T., broken face
- 26" B. Oak N 73°W 6.6', O.B.T., rotted face
- 12" D. Fir S 54½°E 21.9' (rec. 21.7') healed
- 11" B. Oak S 86°W 44.6' (rec. 44.75') healed

SE Cor. Section 12 found B.L.M. 1963 brass cap on 2" G.I. Pipe, & B.T.'s by County Surveyor:

- 40" W. Oak N 37½°E 95.7', healed
- 18" I. Cedar S 22°E 13.9', healed

21" I. Cedar S67½°W 38.9', healed
 23" I. Cedar N 7°W 31.0', healed
 4' high x 9'x 9' Boulder S 46°E 80.5'

East 1/16 Cor. Secs. 1 & 12 set 5/8" I.Rod, scribe "E 1/16S
 (Sec. No.) 1358 BT" on:
 8" I. Cedar N 45½°E 28.0'
 6" D. Fir S 86°E 25.9'

NE 1/16 Cor. Sec. 12 set 5/8" I. Rod, scribe "NE 1/16S 12
 1358 BT" on:
 9" D. Fir S 52°W 27.8'
 8" D. Fir S 54°E 14.6'

CE 1/16 Cor. Sec. 12 set 5/8" I.Rod, scribe "CE 1/16S 12
 1358 BT" on:
 6" D. Fir S51°W 25.7'
 14" P. Pine S 31½°E 56.1'

East 1/16 Cor. Secs. 12 & 13 set 5/8" I.Rod, scribe "E 1/16S
 (Sec. No.) 1358 BT" on:
 9" D. Fir N 82°W 30.5'
 8" P. Pine S 49°W 40.7'

3 Corners of the 330'x 660' O.R. 80-19936 property, set 5/8"
 I.Rod, scribe B.T.'s. as follows:

SW Cor. scribed "PC #2 1358 BT" on:
 14" D. Fir S 61°W 8.8'
 14" P. Pine N 42½°W 22.4'

NW Cor. scribed "PC #3 1358 BT" on:
 10" I. Cedar S 76½°W 37.4'
 6" I. Cedar S 46°E 13.8'

NE Cor. scribed "PC #4 1358 BT" on:
 6" W. Oak N 29°W 10.2'
 10" W. Oak S 22°W 21.4'

¼ Cor. Secs. 14 & 13 found Survey # 6530 5/8" I. Rod w/Yel. cap
 "Thompson RE 3683" and B.T.'s.:
 21" W. Oak N 33°E 44.2', O.B.T., dim scribe vis.
 10" D. Fir S 44°E (rec. S 37° 45'E) 11.95', scribe part vis.
 12" W. Oak N 21° 45'W 23.8', healed

Cor. Secs. 13,14,23,24 found 1963 B.L.M. br. cap on 2" G.I. Pipe
 and B.T.'s.: (1963 except O.B.T.'s)
 26" B. Oak N 71°E 32.3', O.B.T., healed
 17" B. Oak S 48°E 75.1' (rec. 75.9') O.B.T., healed
 27" B. Oak S 48°W 26.4', O.B.T., healed
 18" D. Fir N 65½°E 30.8', (rec. 29.7'), healed
 12" D. Fir S 12°E 40.3', healed
 8" D. Fir S 61½°W 61.4', healed
 16" D. Fir N 57½°W 36.6', healed

¼ Cor. Secs. 14 & 23 not found, set 5/8" I. Rod, scribed B.T.'s.
 "¼S (Sec. #) 1358 BT" on:
 12" D. Fir N 26½°W 37.8'
 12" D. Fir S 65°E 47.8'

Cor. Secs. 14,15,22,23 found 1976 Co. Surveyor br. cap on 1" G.I.
 Pipe, in meadow and B.T.'s.: (1976 except O.B.T.'s)
 30" B. Oak N 40°E 154.4' on slope, O.B.T., dead & down
 40" B. Oak S 52¼°E 282.5' (rec. S 55°E 275.9') O.B.T. rotted and
 burnt out
 40" W. Oak S 80°W 108.2', O.B.T., rotted stump
 23" P. Pine N 46°E 131.9', healed
 10" Quadruple W. Oak S 85°E 189.6', healed
 18"x32" Forked B. Oak N 51½°W 77.8', healed
 Scribed additional B.T."T34S R2W S 14 1358 BT":
 9" S. Pine N 74°E 110.1'

1/4 Cor. Secs. 15 & 14 not found, set 5/8" I. Rod, scribed B.T.'s.

"1/4 S (Sec. No.) 1358 BT" on:

6" D. Fir N 24 1/2°W 3.3'

6" D. Fir N 67°E 15.0'

N 1/16 Cor. Secs. 15 & 14 set 5/8" I. Rod, scribed "N 1/16S

(Sec. No.) 1358 BT" on:

10" P. Pine S 68°W 61.7'

17" W. Oak S 28°E 58.2'

Center 1/4 Cor. Section 14 set 5/8" I. Rod, scribed B.T.'s.

"C 1/4 S 14 1358 BT" on:

11" D. Fir N 58°E 29.4'

12 D. Fir S 37 1/2°E 34.8'

Cor. Secs. 15,16,21,22 found 1958 B.L.M. br. cap on 2" G.I. Pipe on E-W fence line, and B.T.'s.: (1958 except O.B.T.'s)

32" Pine N 40°E 6.6', O.B.T., down & dead, scribe part vis.

40" Pine S 70°W 11.9', O.B.T., down, dead, rotted, BT face vis.

12 " D. Fir N 36°E 79.2', healed

12" Oak S 83°E 82.8' (rec. 83.8'), healed

6" Oak S 39°W 58.7', healed

16" D. Fir N 9°W 44.9' (rec. 45.5'), healed

Cor. Secs. 9,10,15,16 found 1976 Co. Surveyor br. cap on 1" G.I. Pipe and B.T.'s.: (1976 except O.B.T.'s)

11" W. Oak N 35°E 43.6' (to ctr., rec. 40.9') O.B.T., scribe vis.

26" D. Fir S 30°E 52.8', O.B.T., dead & down on face

12 " W. Oak S 80°W 62.7', O.B.T. stub, rev. scribe pt. vis.

8" W. Oak N 55 1/2°E 14.4', scribe part vis.

7" W. Oak S 84°E 49.8', scribe vis.

6" D. Fir S 33 1/2°W 32.8', scribe vis.

4" W. Oak N 74 1/2°W 8.9', scribe vis.

W 1/16 Cor. Secs. 10 & 15 set 5/8" I. Rod, scribe B.T.'s "W 1/16S

(Sec. No.) 1358 BT" on:

9" W. Oak N 44 1/2°E 12.0'

9" P. Pine S 12 1/2°W 14.9'

1/4 Cor. Secs. 10 & 15 not found, set 5/8" I. Rod, scribed B.T.'s

"1/4 S (Sec. No.) 1358 BT" on:

13" D. Fir N 51°E 13.7'

14" D. Fir S 29°E 42.2'

East 1/16 Cor. Secs. 10 & 15 set 5/8" I. Rod, scribed B.T.'s

"E 1/16S (Sec. No.) 1358 BT" on:

12" D. Fir N 59°E 35.15'

11" P. Pine S 52°E 44.7'

NE 1/16 Cor. Sec. 15 set 5/8" I. Rod, scribed B.T.'s "NE 1/16S 15

1358 BT" on:

9" D. Fir N 68°W 32.5'

14" P. Pine S 26 1/2°E 27.8'

CE 1/16 Cor. Sec. 15 set 5/8" I. Rod, scribed B.T.'s "CE 1/16S 15

1358 BT" on:

12" D. Fir N 32°W 14.3'

11" I. Cedar N 68°E 31.9'

August 1, 1984

