

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: LOUISIANA-PACIFIC CORP.
P.O. BOX 711
LAKEVIEW, OR 97630

LOCATION: SECTION 33, TOWNSHIP 36 SOUTH, RANGE 1 EAST,
WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON.

PURPOSE: TO SURVEY AND MARK PROPERTY LINES AS SHOWN ON
THE ATTACHED MAP.

PROCEDURE: AT THE NORTHWEST CORNER OF SECTION 33 I FOUND
A MOUND OF STONE, THE REMAINS OF A BEARING
TREE IN THE SOUTHEAST QUADRANT AND THE ROOT
HOLE OF THE BEARING TREE IN THE SOUTHWEST
QUADRANT. THE ORIGINAL TREE IN THE SOUTHEAST
QUADRANT HAD BEEN BURNED ENOUGH THAT THE SCRIBE
COULD NOT BE FOUND. TO VERIFY THAT THE STONE
MOUND WAS IN THE CORRECT LOCATION, I RAN A
TRAVERSE WEST TO THE NORTH ONE-QUARTER CORNER
OF SECTION 32. WITH THIS INFORMATION IN HAND
I WENT TO THE COUNTY SURVEYOR'S OFFICE. RON
FROST OF THE COUNTY SURVEYOR'S OFFICE MADE A
FIELD CHECK WITH ME. WITH PREVIOUS INFORMATION
THAT THEY HAD PLUS MY CURRENT DATA, THEY ACCEPTED
THE POSITION OF THE STONE MOUND AND SET A BRONZE
CAP ON A ONE INCH PIPE FOR THE CORNER.

WHILE MR. FROST WAS IN THE AREA HE SET A BRONZE
CAP ON A ONE INCH PIPE AT THE EAST ONE-QUARTER
CORNER OF SECTION 33. BOTH ORIGINAL BEARING
TREES HAD BEEN FOUND AND A TRAVERSE RAN SOUTH
TO THE SOUTHEAST CORNER OF SECTION 33 VERIFIED
THE POSITION OF THE CORNER.

AT THE SOUTH ONE-QUARTER CORNER I FOUND THE
ORIGINAL BEARING TREE IN THE NORTHWEST QUADRANT.
FROM SAID TREE I WENT SOUTH 08° EAST 80.52 FEET
(RECORD 122 LKS) AND SET A $5/8$ " IRON PIN WITH
A PLASTIC CAP STAMPED MOFFIT PLS 944 AT THE ONE
QUARTER CORNER OF SECTION 33, FROM WHICH;

A $5/8$ " IRON PIN BEARS $S63^{\circ}E$ 28.58 FEET

A SEARCH WAS MADE FOR EVIDENCE OF THE WEST ONE-
QUARTER CORNER OF SAID SECTION 33, NOTHING WAS
FOUND. THEREFORE, AT THE PROPORTIONED POSITION
OF THE ONE-QUARTER CORNER, I SET A $5/8$ INCH
IRON PIN WITH A PLASTIC CAP STAMPED MOFFIT
PLS 944, FROM WHICH;

A 9" OAK BEARS $S65^{\circ}E$ 18.70' SCRIBED 1/4S 33 BT

A 7" OAK BEARS $N76^{\circ} 30'W$ 66.22' SCRIBED 1/4
S32 BT

AT THE WEST ONE-SIXTEENTH CORNER ON THE SOUTH
LINE OF SAID SECTION 33 I SET A $5/8$ INCH IRON
PIN WITH A PLASTIC CAP STAMPED MOFFIT PLS 944,
FROM WHICH;