



SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250  
OREGON REVISED STATUTES

SURVEY FOR: Weyerhaeuser Company  
c/o Real Estate Services  
attn: David M. Judkins  
Real Estate Manager  
Tacoma, Wa. 98477

LOCATION: Donation Land Claim 66, Section 15 in Township 37  
South, Range 2 West, Willamette Meridian, Jackson  
County, Oregon


PURPOSE: Lot line adjustment between Tax Lots 1600 and 1801  
and acreage computation prior to purchase

PROCEDURE: The property is bounded on the South by the South boundary of  
Donation Land Claim 66, and on the West by the County Road and the 15 foot strip  
deeded to Jackson County by Instrument No. 78-22258. The monuments set in Sur-  
vey 8002 to mark this strip were located and their location verified.

The North boundary is described by deed as being the centerline  
of the Hopkins Canal. The apparent centerline of the canal was located and com-  
pared to record location. There appeared to be some significant discrepancies  
between the two locations, and the apparent physical centerline was held as con-  
trolling. The monument set near the Southeast corner of Survey No. 479 and de-  
scribed as being "140.0 feet North of center of ditch" was searched for but not  
found.

The Easterly boundary was located along Griffin Creek. However,  
this boundary is intended to be controlled by bearings and distances, and not  
intended to follow the actual centerline of the creek.

August 29, 1984



Roger R. Roberts  
Hoffbuhr/Bath & Associates, Inc.  
219 North Oakdale  
Medford, Oregon 97501