



PROPERTY Situate in
 Section 10, Twp. 37.S.R. 2 W.W.M.,
 JACKSON COUNTY, OREGON
 J. H. CLABBY CIVIL ENGINEER
 Medford, Ore. JULY 20, 1956

SCALE: 1" = 100'



N.W. Cor. D.L.C. 66

Survey Narrative to Comply with Section 87-330, 1947 Oregon Law.

Survey for: Mr. Henry Sandvig

Location: Section 10, Township 37 South, Range 2 West, Willamette Meridian in Jackson County, Oregon.

Purpose of Survey:

To survey and describe four parcels of land lying west of Grant Road and north of Beall Lane.

Procedure: Found northwest corner of D.L.C.No. 66, found pipe monuments established on previous surveys on north right of way line of Beall Lane and westerly right of way line of Grant Road.

A - Established south line of D.L.C. No. 54 and center line of Grant Road. Intersected the above lines at a point South $89^{\circ} 53'$ West from said northwest corner of D.L.C.No. 66. From said intersection ran North $14^{\circ} 53'$ West 540 feet along center line of Grant Road and set nail in pavement, thence South $89^{\circ} 53'$ West 181.45 feet and set iron pin, thence South $0^{\circ} 07'$ East 522.40 feet to said D. L. C. line and set nail in pavement, thence North $89^{\circ} 53'$ East 318.96 feet to point of beginning - 3.000 acre more or less.

B - From said D.L.C. corner ran South $89^{\circ} 53'$ West 763.56 feet along D.L.C. line for the true point of beginning, thence continue South $89^{\circ} 53'$ West 193.25 feet, thence North $0^{\circ} 07'$ West 522.40 feet, thence North $89^{\circ} 53'$ East 193.25 feet, thence South $0^{\circ} 07'$ East 522.40 feet to the point of beginning. Containing 2.318 acres more or less.

C - From said road intersection ran North $14^{\circ} 53'$ West 540 feet along center line of Grant Road for true point of beginning, thence continue North $14^{\circ} 53'$ West 136.67 feet, thence South $89^{\circ} 53'$ West 351.04 feet, thence North $0^{\circ} 07'$ West 132.15 feet, thence North $89^{\circ} 53'$ East 351.04 feet to the point of beginning. Containing 1.118 acres more or less.

D - From said road intersection ran North $14^{\circ} 53'$ West 676.67 feet along center line of Grant Road for the true point of beginning, thence continue North $14^{\circ} 53'$ West 135.00 feet, thence South $89^{\circ} 53'$ West 316.64 feet, thence South $0^{\circ} 07'$ East 130.54 feet, thence North $89^{\circ} 53'$ East 351.04 feet to the point of beginning. Containing 1.000 acres more or less.

August 3, 1956

J. H. Clabby

