



### MAP

SHOWING A SURVEY AND TOPOGRAPHIC SURVEY  
 IN THE NE 1/4 OF THE NW 1/4 OF SECTION 22,  
 T. 36 S., R. 4 W., W.M., JACKSON CO., OREGON  
 FEBRUARY 12, 1985  
 SCALE: 1" = 20'

SURVEYED FOR:  
 KELLENBECK CONSTRUCTION  
 830 NE VICTORIA  
 GRANTS PASS, OREGON

SURVEYED BY:  
 MAX H. HULL, SURVEYING  
 231 NW "B" STREET  
 GRANTS PASS, OREGON



- x — FENCELINE
- FD. MONUMENT AS NOTED
- SET 5/8" X 30" IRON ROD WITH YELLOW PLASTIC CAP STAMPED MS 901 HULL
- SURVEY NARRATIVE SEPARATE
- BASIS OF BEARING CS 6838

RECEIVED  
 Date \_\_\_\_\_ By \_\_\_\_\_  
 This survey consists of \_\_\_\_\_ sheet(s) of \_\_\_\_\_  
 part(s) of \_\_\_\_\_  
 JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR  
 MAX H. HULL  
 901



**MAX H. HULL Land Surveying**

10203

Office 476-2425

231 N. W. 'B' Street Grants Pass, Oregon 97526

SURVEY NARRATIVE to comply with Paragraph 209.250, O.R.S.

DATE: February 12, 1985

FOR: Kellenbeck Construction  
830 NE Victoria  
Grants Pass, OR 97526

PURPOSE: To survey and monument a parcel of land located in the Northeast Quarter of the Northwest Quarter of Section 22, Township 36 South, Range 4 West of the Willamette Meridian, Jackson County, Oregon.

PROCEDURE: Finding monuments per County Survey No. 6838 as indicated on the map, I also surveyed to monuments found per County Surveys 8447 and 9637 as shown; thence using the record deed description, I surveyed the East, South and West boundaries as shown on the map. The bearing calls in the deed do not coincide with the distance calls. I determined the position of the Interior Southwest corner by using a distance, distance line intersect.

Meridian is based on the East line of Survey No. 6838.

Survey plat accompanys this survey narrative.

