



N

BASIS OF BEARINGS: R.S. 4269

DETAIL SCALE: 1" = 100'

**** RECEIVED ****

Date: 3/21/85 By SK

This survey consists of:

1 sheet of plan

1 map of location

LAND SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR

Darrel W. Edwards

GREGON

DARREL W. EDWARDS

741

SURVEY FOR: Adams & Bunn

SCALE: 1" = 1000' () USGS Rec. meas. unless noted

DATE: Mar. 20, 1985 x-x-x Fence Line

LOCATION: Section 6, Township 40 S., Range 3 E., W.M. in Jackson County, Oregon.

● Monument found as noted

○ 5/8" x 24" steel pin set except where noted

DRAWN BY BQE

DRAWING NUMBER

NOTE: Acreages in NE 1/4, SW 1/4 are computed to Tyler Creek Road.

SURVEY NO. 10213

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250, OREGON REVISED STATUTES.

SURVEY FOR: Adams, Gregg & Bunn, Dan
728 Cardley Avenue
Medford, Ore. 97504

LOCATION: Section 6, Township 40 South, Range 3 East of the Willamette Meridian in Jackson County, Oregon.

PURPOSE: Survey Tax Lots 3100, 3101 and 3102 in Said Section 6.
Also to locate County Road and dirt access road.

PROCEDURE: Made ties to Government corners along perimeter of said Section 6. Calculated corner positions and set 5/8" x 2 1/2" steel pins with plastic caps as shown on the accompanying plat.

Set SW 1/16 corner, from which a 10" Oak bears S. 65°30' E. 18.35' and an 8" Oak bears S. 62° 30' W. 24.30'.

Set CS 1/16 corner, from which a 5" Oak bears S. 35° E. 10.94' and a 10" Oak bears S. 30° W. 10.90'.

Set Center 1/4 corner, from which a 4" Oak bears N. 19° 30' W. 10.95'; 5" Oak bears N. 68° E. 9.70'; 5" Oak bears S. 44° 45' W. 15.32'; 4" Oak bears S. 2° 30' E. 20.00'.

EQUIPMENT: Lietz TM-20C theodolite, Lietz Red-1 EDM and 200' tape.

BASIS OF BEARINGS: RS 4269

Date Completed: March 20, 1985.

SURVEY BY: Darrel W. Edwards
728 Cardley Avenue
Medford, Ore. 97504
Phone 776-2313

